

SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY AND MANUFACTURES.

Vol. XLV.—No. 6.
[NEW SERIES.]

NEW YORK, AUGUST 6, 1881.

\$3.20 per Annum.
[POSTAGE PREPAID.]



1.—Pasture and Watering Place for Cattle. 2.—Slaughter House. 3.—Boiler House. 4.—Condensers. 5.—Hall for Salting the Tasso. 6.—Tallow Trying. 7.—Fertilizer Packing. 8.—Dock.

LIEBIG'S EXTRACT OF MEAT.—MANUFACTORY AT FRAY BENTOS (SOUTH AMERICA).—(See page 84.)

Scientific American.

ESTABLISHED 1845.

MUNN & CO., Editors and Proprietors.

PUBLISHED WEEKLY AT
NO. 37 PARK ROW, NEW YORK.

O. D. MUNN.

A. E. REACH.

TERMS FOR THE SCIENTIFIC AMERICAN.

One copy one year postage included. \$3 20
One copy, six months postage included. 1 60
Clubs.—One year copy of THE SCIENTIFIC AMERICAN will be supplied gratis for every club of five subscribers at \$1.20 each; additional copies at same proportionate rate. Postage prepaid.
Remit by postal order. Address

MUNN & CO., 37 Park Row, New York.

The Scientific American Supplement

Is a distinct paper from THE SCIENTIFIC AMERICAN. THE SUPPLEMENT is issued weekly. Every number contains 16 octavo pages, uniform in size with THE SCIENTIFIC AMERICAN. Terms of subscription for SUPPLEMENT, \$3.00 a year, postage paid, to subscribers. Single copies, 10 cents. Sold by all news dealers throughout the country.

Combined Rates.—THE SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for one year postage free, on receipt of seven dollars. Rush papers to one address or different addresses as desired.

The safest way to remit is by draft postal order, or registered letter. Address MUNN & CO., 37 Park Row, N. Y.

Scientific American Export Edition.

The SCIENTIFIC AMERICAN Export Edition is a large and splendid periodical, issued once a month. Each number contains about one hundred large quarto pages, profusely illustrated, embracing: (1.) Most of the plates and pages of the four preceding weekly issues of THE SCIENTIFIC AMERICAN, with its splendid engravings and valuable information; (2.) Commercial, trade, and manufacturing announcements of leading houses. Terms for Export Edition, \$5.00 a year, sent prepaid to any part of the world. Single copies 10 cents. (3.) Manufacturers and others who desire to secure foreign trade may have large and handsomely displayed announcements published in this edition at a very moderate cost.

The SCIENTIFIC AMERICAN Export Edition has a large guaranteed circulation in all commercial places throughout the world. Address MUNN & CO., 37 Park Row, New York.

NEW YORK, SATURDAY, AUGUST 6, 1881.

Contents.

(Illustrated articles are marked with an asterisk.)

Acid sulphuric, dangers of.....	50
Annunciator, speaking tube.....	51
Antimony, American.....	51
Aquarium, ornamental.....	51
Belt, telephone, independent.....	51
Blue furnace, new.....	51
Bottle, steam, notes.....	51
Car starter, improved.....	51
Chilled meteor, the.....	51
Cold air machine, Presidential.....	51
Comet, another, discovered.....	51
Conductor's printing office, a.....	51
Diagrams.....	51
Drop press, new.....	51
Drying cylinder, steam, expansion.....	51
Electrical exhibition, Paris.....	51
Electricity, used by.....	51
Engineering inventions.....	51
Exhaust steel, for.....	51
Extract of meat, Lager's.....	51
Factors, preservation of.....	51
Fencing in iron ships.....	51
Gelatin emulsion, making.....	51
Ground glass, imitation.....	51
Hay rack, shattering.....	51
Headache, nervous.....	51
Industries of New York.....	51
Link for rubber stamps.....	51
Inventions, engineering.....	51
Inventions, mechanical.....	51
Inventions, miscellaneous.....	51
Inventions, recent.....	51
Iron, to remove stains from.....	51
Leach farm, a.....	51
List of extracts of meat.....	51
Lighting, protection from.....	51
Med. List of extracts of meat.....	51
Mechanical inventions.....	51
Mechanics, educated.....	51
Meteor, Chilat, the.....	51
Microphone, phosphorus, a.....	51
Moles, how they aid agriculture.....	51
Monolith, large, a.....	51
Mother of pearl.....	51
Oil to extract from herbs.....	51
Pale, strong, a.....	51
Patents in Turkey and Liberia.....	51
Pearl industry.....	51
Pharaoh's serpent and sea snake.....	51
Pistol, toy, and lockjaw.....	51
Portrait, composite.....	51
Printing office, a conductor's.....	51
Railway safety, new.....	51
Railway travel, risks of.....	51
Sea lamprey, the.....	51
Ships, iron, sinking in.....	51
Silicon in steel rails.....	51
Speaking tube annunciator.....	51
Steam boiler notes.....	51
Sulphuric acid, dangers of.....	51
Telegraph, first in this country.....	51
Telephone, first, underground.....	51
Telephone, first, underground.....	51
Toy pistols and lockjaw.....	51
Wagon, steam.....	51
Water, hot, for the heart.....	51
Waterproofing.....	51

TABLE OF CONTENTS OF

THE SCIENTIFIC AMERICAN SUPPLEMENT

No. 292,

For the Week ending August 6, 1881.

Price 10 cents. For sale by all newsdealers.

	PAGE
I. ENGINEERING AND MECHANICS. —French Candle Moulding Machine. 2 plates, 30 figures.—Moran's candle-moulding machine. 1 plate, 10 figures.	458
The Canal System of New York. (Continued from No. 291.) Water supply.—Depth and flow.—Steam propulsion.—Canal business.—Comparative table.—Proposed improvements.	459
On Harrowing Machinery. By E. SANFORD. (Continued from No. 291.) Wire binding mechanism.—Striking binding mechanism.	463
The Mercury Railway Tunnel. 6 figures.—Section of tunnel.—Driftway and shafts.—Passenger ferry now in use.—Ferry for vehicles.—Map showing position of tunnel.—Working at the face of the heading.—View of Hickenhead Works, etc.—Working at bottom of shaft.—Going down in the bucket.	465
The Electric Railway of Lyons.—Lichterfeld, near Berlin. 1 figure.—Stationary Steam engine coupled with the Siemens dynamo-electric machine.—The electric railway.	468
Links in the history of the Locomotive. 1 figure.—Murdock's locomotive, 1825.	469
Torquato of New Mexico. By B. SULLIVAN. 1 figure.	470
II. TECHNOLOGY AND CHEMISTRY. —Textile Fibers under the Microscope. 2 figures.—Views showing the distinctive characteristics of the various textile fabrics.	467
Straw and Wire Goods in Tension.	468
New Discovery Regarding Gelatine Emulsions. By L. W. BARTHELEME.	471
A Drying Cabinet. 1 figure.	472
Fisher's dynamo. 1 figure.	473
Molecular Activity and Decomposition of Matter. By O. KELLER.	474
Wunderlich's Process for the Preservation of Organic Substances. By H. STREUMER and O. JACOBSEN.	477
Water in Gases.	478
Preliminary Notice of a New Vegetable Coloring Matter. By SAM. P. HARRINGTON and W. L. HOWLAND.	479
A Case of Decoloring of Carbonic Acid.	480
Apparatus for Continuous Distillation. 1 figure.	481
Distillation of Liquefied Oxygen. Hydrogen and Nitrogen. By L. C. HARTLEY and P. HARTLEY.	482
Japanese Mill. 1 figure.	483
Distillation of Benzol. 1 figure. Haywood and Baron's Mill.	484
The Influence of Water and their Influence upon the Growth of Plants. By J. E. JOHNSON.	485
Automatic Washing of Potatoes. 1 figure.	486
Hemoglobin and its Distribution in the Animal Kingdom. By F. E. W. MUELLER.	487
On the Conduct of Finely-divided Iron toward Nitrogen. By H. A. REMY.	488
Spontaneous Ignition of Coal. By H. REMY.	489
Statistics of Salty Acid. By E. F. SMITH.	490
On Pure Coke. By W. S. STAVELY.	491
Sodium and Potassium Chlorides in Mineral Analysis. By J. P. MUELLER.	492
III. PHYSICS AND PHYSICAL APPARATUS. —Torsion Pendulum Balance. 1 figure.—Gorham's Dispensing Balance. 1 figure.—A New Lactometer. 1 figure.—Schuler's Lactometer. 1 figure.—A New Lactometer. 1 figure.—Experimental Determination of the Velocity of White and Colored Light. By Dr. J. VORHIES and Prof. G. VORHIES.	493
Photographic Science Reviewers. How made.	494
IV. NATURAL HISTORY, ETC. —Opportunity. Eating of a full-grown Water Moccasin (Amphibian) by the King Snake (Ophichthus) etc.	495
Street Trees and Public Grounds. The best trees for street shading, and how they should be planted.	496

venting train robberies in the East as in England, than anything in the construction of the cars or the make up of the trains. Given equal time for the work, we are inclined to think that fewer men would be required to capture and go through a train of English cars than one of American cars, while the robbers' chance of meeting serious resistance on the latter would be much the greater. But this question of comparative immunity from attack plays a very insignificant part in determining the choice of large or small compartments, compared with popular customs, popular habits of thought with respect to privacy or promiscuity, the varying hazard of undesirable social contacts while traveling, and all that sort of thing. The English have their prejudices as Americans have theirs, and matters of this sort are more apt to be decided by prejudice than by the calculation of infinitesimal risks to life or property.

PATENTS IN TURKEY AND LIBERIA.

General patent laws have been lately passed and promulgated in Turkey and Liberia, in which countries American citizens may now, for the first time, secure their new inventions.

The Turkish patent law is substantially a copy of the French and German systems. Any person may take a patent on deposit of drawings and specifications. Longest term of the patent fifteen years, annual tax \$18. The invention must be worked within two years from the date of the patent. The penalties for infringement and the proceedings are the same as in European countries.

In Liberia the patentee must be the inventor, or must have lawfully acquired the invention from the inventor. Drawings and specifications must be furnished. The government fee is fifty dollars. The proceedings are much the same as in taking an American patent. The invention must be worked within three years after the grant of the patent. Those desiring to obtain patents in either of the above countries may obtain further information at this office.

WATERPROOFING.

Without considering the processes by which cloth is waterproofed with such substances as India-rubber, oils, wax, and varnishes, there are several processes in practical use by which cloth is rendered non-absorbent of water—and for all practical purposes waterproof—without materially affecting its color or appearance, greatly increasing its weight, or rendering it entirely airproof. These processes depend mainly upon the reaction between two or more substances, in consequence of which a substance insoluble in water is deposited in the fibers of the cloth.

The following are several of these processes:

LOWRY'S PROCESS.

Soap.....	2 ounces.
Gum.....	4 "
Water.....	1 gallon.

Soften the glue in cold water and dissolve it together with the soap in the water by aid of heat and agitation.

The cloth is filled with this solution by boiling it in the liquid for several hours, the time required depending upon the kind of fiber and thickness of the cloth. When properly saturated the excess of liquid is wrung out and the cloth exposed to the air until nearly dry; then digested for from five to twelve hours in the following solution:

Alum.....	15 ounces.
Salt.....	15 "
Water.....	1 gallon.

It is finally wrung out, rinsed in clean water, and dried at a temperature of about 80° F.

Paul's process requires a small quantity of oil, but in other respects resembles the last. It is given as follows:

Boiling castor-oil (com.).....	1 pound.
Caustic lime.....	15 "
Water.....	1 gallon.

Boil together, let it stand to settle, then draw off the clear, and add to it—

Boiling castor-oil.....	4 pounds.
Boiling water.....	1 gallon.

previously melted together. Boil and stir occasionally for half an hour, then introduce—

Glue (previously softened).....	3 ounces.
Essential oil.....	5 "

and continue the boiling and stirring for another half hour.

In waterproofing one-half ounce of this soap is mixed with a gallon of hot water, and in this the goods are soaked for about twenty-four hours, according to the thickness and character. The pieces are then allowed to drain until partly dried, then soaked for six hours or more in a solution prepared as follows:

Aluminum sulphate.....	1 pound.
Lead acetate.....	1/2 "
Water.....	5 gallons.

Shake together, allow to settle, and draw off the clear liquid.

Wring out after rinsing, and dry at a temperature of 80° F.

Rienvaux uses, instead of glue and oil as above, the gelatinous portion of sea-wrack grass with a small quantity of a drying oil and common train soda soap.

In Riemann's process the cloth is passed slowly by machinery through a tank divided into three compartments, the first containing a warm solution of alum, the second a warm solution of lead acetate, and the third pure water, which is constantly renewed. The cloth on passing from the latter is brushed and beaten to remove the salt adhering

to the surface, and finally hot pressed and brushed. In this case lead sulphate is deposited in the fibers.

In Townsend's process two solutions are used as follows:

British gum.....	20 pounds.
Soap, white.....	10 "
Water.....	10 gallons.

The solution is boiled for some minutes, and if color is required one pint of logwood liquor is added. The second solution consists of a saturated solution of alum in water, or—

Zinc sulphate.....	6 pounds.
Water.....	2 gallons.

Ballard's process is somewhat similar to Riemann's. In this strong aqueous solutions of sulphate of aluminum and lead acetate are used alternately.

Berlin waterproof cloth is said to be prepared by saturating the cloth in a solution of acetate of aluminum and copper, then dipping it successively in water glass and resin soap.

MOTHER-OF-PEARL AND PEARL INLAYING.

Mother-of-pearl is chiefly obtained from the pearl oyster (*Meleagrina margaritifera*) which is found in the Gulf of California, at Panama, Oubagun, Ceylon, Madagascar, Swan River, Manila, and the Society Islands. The black-lipped shells from Manila are most highly prized. The Society Islands furnish the silver-lipped sort, and Panama the "bullock" shells.

The genera *Halotus*, *turbo*, etc., also furnish some mother-of-pearl. Technically the mother-of-pearl obtained from the pearl oyster is known as white pearl; that of *Halotus* or *senar* as aurora or ear shell; it is easily distinguished from the former by its prismatic colors and wrinkled appearance.

The peculiar and varied tints exhibited by mother-of-pearl is due to the structure of its surface, which, owing to the great multitude of minute grooves upon it—often many thousands to the inch—decomposes the light which falls upon it and reflect different hues.

The pearl shell is lamellar in structure, and admits of being split into laminae, but this method of dividing it is seldom resorted to owing to the liability of spoiling the shell.

In working up mother-of-pearl the saw file, and grindstone are the principal tools employed. A shell is selected with a coating of the substance of a thickness as nearly as possible to suit the required purpose. Square or angular pieces are cut out with a small circular or buck or fret saw to suit convenience, the piece being held and manipulated with the hand or clamped in a vise. Buttons and such circular pieces are cut with an annular or crown saw fixed upon a mandrel. All such tools used in cutting pearl must be kept well moistened with water to prevent over-heating. The pieces are usually dressed upon a grindstone, the edge and face of which are grooved or ridged to prevent clogging. The stone is kept wet when in use; for this purpose weak soapsuds is better than water alone.

When the pieces have been properly shaped on the stone they are dressed with pumice stone and water. In some cases the better plan is to have the piece of pumice stone shaped so as to adapt it to the form required and held in a vise while the work, held in a clamp, is revolved in contact with it on the lathe. After the application of the stone fine powdered pumice stone, free from coarse grit, is applied with a cork or cloth moistened with water. In the final polishing rotten stone is employed. This is moistened with dilute sulphuric acid (1 acid, 15 water) and applied with a cork. The acid is said to develop finely the striated structure of the shell. In some works it is thought necessary to use emery before the rotten-stone and to use a linseed oil in place of the acid.

Knife and razor handles of pearl, after having been roughed out, are drilled where the rivets are to be inserted, lightly riveted together, shaped on the stone, and finished as above described, the last finishing touch often being done by friction of the hand of the workman.

In some shops much of the polishing is done on cloth-covered wheels, the moist cloth carrying the polishing materials. Separate wheels are used for the different materials. For some common work powdered chalk or Spanish whiting is used in place of rotten stone.

Pearl is etched by a process very similar to that used in etching copper. The designs or patterns are drawn upon it with asphaltum varnish, and all parts not intended to be etched having been similarly protected, the piece is submitted to the action of nitric acid. When the parts unprotected have been sufficiently eaten away by the acid the piece is rinsed in cold water and the varnish washed off with a little turpentine or benzine.

Thin pieces of mother-of-pearl of a like pattern are usually gung cut; that is, the thin plates are glued together, then held in a clamp and cut, drilled, and dressed as one piece, after which they are separated by being thrown into hot water, which separates the glue.

In common pearl-inlay work, films or very thin pieces of mother-of-pearl are connected to a background, usually of papier mâché or iron, by Japan varnish. The plate having been cleaned and dried receives a coat of the varnish and when this is nearly dry the pieces of pearl, cut out with a scissors by the artist to represent leaves or designs, are pressed against and adhere to the varnish. The plate is then put in the Japanese oven until the coating becomes hard. A second coating of varnish is then put on—indiscriminately over the pearl and all—and when this has been dried or hardened in the oven the portions adhering to the pearl pieces are removed

with a knife blade, and the whole surface is rubbed smooth with pumice stone and water. With the aid of a little gold size, gold leaf, and color, and camel's-hair brush the artist then develops the design, the beauty of which depends of course upon his skill. Finally the article receives a coat of clear spirit varnish.

Besides the white and aurora shell referred to above, the glistening green snail shell is very frequently used. Its tints are light and dark green, yellow, and pink, blended. The varnished surface is sometimes ornamented with transferred drawings or engravings. When the varnish is nearly dry the engraving is spread out face downward upon it and carefully pressed so as to exclude air bubbles. After the varnish is thoroughly dry the paper is well moistened with warm water by means of a sponge. It may then be rubbed off, the lines of the print remaining adhering to the varnish.

THE PARIS ELECTRICAL EXHIBITION.

Among the promised novelties connected with the exhibition will be a boat propelled by electricity. For this purpose there will be a water basin fifty feet in diameter, in which the boat will be kept moving. In the center of the basin, on a pedestal, will be a brilliant electric light. At various points within the palace models of statues will be placed as supports for electric lights. Each exhibitor of lights is also to have a saloon set apart for the special show of his system.

The passenger station of the electric railway will be within the exhibition building, and the track will run on the ground—not elevated as at first intended.

During the exhibition there will be a congress of electricians, of which sixty-five French members have been appointed by the President of the Republic. The congress will publish an official report, and only members will be allowed to be present.

Another Comet Discovered.

Mr. J. M. Schaeberle, of Ann Arbor, Mich., discovered, July 13, a new comet, the third of 1881. In the telescope it showed a bright center and a clear though faint tail. It appeared in the northeast, in the constellation Auriga, not far from the point of appearance of the comet now passing out of sight. The new comet is rapidly increasing in brightness, and will continue to do so until about the 21st of August, when it promises to be quite conspicuous, certainly as a telescopic object. It will be nearest the earth about August 20, a day or two after its perihelion passage, when it will be about 40,000,000 miles away. So far "the orbit presents no special resemblance to that of any known comet," the Harvard astronomers say, though Professor Houze, of Cincinnati, thinks he finds in it a close resemblance to that of the great comet of 1337. It seems to be moving in a northerly direction.

American Antimony.

A Baltimore dispatch informs us that a carload of antimony, ten tons in all, was on the 14th of July received by C. L. Oudeshops & Co., from the southern part of Utah Territory being the first antimony received in the East from the mines of that section. The antimony was mined about 140 miles from Salt Lake City. The ore is a sulphide, bluish gray in color, and yields from 60 to 85 per cent of antimony. All antimony heretofore came from Great Britain and the island of Borneo, and paid an import duty of 10 per cent ad valorem, and there is also some from Sonora. It is believed that with proper rail facilities to the mines of the West there will be no need of importations.

Underground Telegraph Line in New York.

The United States Underground Telegraph Company has laid an experimental series of seventy-two wires, extending from the headquarters of the Fire Department, in Mercer street, to Police Headquarters in Mulberry street. The wires are laid in long wooden boxes covered with a preparation of silica and other substances designed to exclude dampness and secure perfect insulation. It is said that if the present experiment is successful the system will be extended so as to include the police stations, engine-houses, and fire-alarm boxes.

Fired by Electricity.

An interesting illustration of the danger attending the manufacture of some kinds of rubber goods was shown to the origin of the recent fire which occurred in the Ethna Rubber Mills, at Jamaica Plain. The cement which fastens the seams of rubber coats is largely made of naphtha. The mere act of lifting a piece of rubber cloth from a pile of half a dozen similar ones, cut for garments, developed so much electricity that a spark was observed to escape. It came in contact with the naphtha cement, or with gases arising from it, and instantly the whole room was in a blaze. Fortunately the fire was extinguished without destroying the mill, the loss being only about a thousand dollars.

It is not known that anything can be done to prevent the occurrence of another accident of precisely the same kind, whenever all the atmospheric conditions are favorable. One would suppose, however, that a certain degree of dampness would remove all danger from that source.—*Commercial Bulletin.*

M. Bouchut's experiments with papain for destroying worms in the stomach and bowels have been continued with extremely promising results. Even the tape-worm succumbs to the digestive action of papain in large doses, while the more highly organized tissues of the stomach are unaffected.

Educated Mechanics.

We have received the twelfth annual and thirteenth statistical report of the Cincinnati Board of Trade and Transportation for 1881, which is a nicely printed pamphlet of two hundred pages.


From Article II. of its constitution it appears that the object of this association is to collect and record such local and general statistical information relating to manufactures and commerce as may promote the manufacturing, commercial, and financial welfare of their city, and especially to protect, foster, and develop its manufacturing and other industrial interests.

After commenting on the success, financially and otherwise, of the Eighth Cincinnati Industrial Exposition, the directors, in their report, insist on the establishment of a school of technology, which their position as a manufacturing community makes peculiarly important. They say:

"The best educated mechanics, and no mechanic is a master of his business without the technical training such schools alone can give. The Exposition Buildings furnish ample room and accommodations for such an enterprise, the Mechanics' Institute School is a good nucleus to start on, the Department of Arts and Sciences of the same institution is a step in advance to the end desired, and this year the exposition should be made the means of enlisting a public co-operation which would provide for Cincinnati just such a school as is needed."

SPEAKING TUBE ANNUNCIATOR.

The engraving shows a novel speaking tube annunciator, in elevation and in section. The tube, A, enters the box,



SPEAKING TUBE ANNUNCIATOR.

B, and terminates behind the hinged drop, C. There may be several tubes and as many drops. Below the drop or series of drops there is a rocker, D, whose arms extend into the box, and are connected by a cord, E, with the trigger of the bell at the top of the box.

When a person in a distant portion of a building wishes to communicate with another who is within hearing distance of the bell he blows in the speaking tube, and the air current thus created being directed against the drop, C, at the other end of such tube, causes it to fall upon the outer bar of the rocker, D. The drop being constructed of a thick metal plate, and therefore heavy, tilts the rocker, as shown in dotted lines, so that it pulls on the cord, E, which, in turn, tilts the lever that raises the hammer, which is instantly released and allowed to fall upon the bell, which gives the required notice. The person thus called will, after responding to the message, close or replace the weighted drop in its upright position, and thus relieve the rocker, which, being released, returns automatically to its former position, and is ready for the next alarm.

This invention was recently patented by Mr. W. R. Ostrander, of New York city.

MOLES—HOW THEY AID AGRICULTURE—HOW THEY CAN BECOME A NUISANCE—HOW THEY MAY BE DESTROYED.

The common ground mole or "meadow mole," as this little animal is often called, is of interest from a zoological point of view, but in this article it is proposed to deal only with the practical side of the subject in its relations to agriculture and horticulture.

The mole is both useful and hurtful. When his services more than counterbalance the injury he commits he should be left unmolested. On the other hand, when he becomes, as he often does, an intolerable nuisance, he may be more or less successfully dealt with in the manner we will proceed to describe.

It is very annoying to see a handsome lawn covered with unsightly ridges plowed by the noses and paws of these little depredators; but the knowledge that they are the natural enemies of the numerous worms and grubs that sometimes make fearful war upon the tender roots of growing young crops, renders it often difficult to decide whether the moles are to be welcomed as allies or combated with such means as are available.

The mole is a purely carnivorous animal, and never does

any damage to plant life except in pursuit of his prey. He may break and disturb the tender roots of young plants, but he does not devour them, and he is often wrongly blamed for injury which has been committed by the insect depredators he has caught and devoured.

The field mouse, on the contrary, does devour tender succulent roots, and the mole is too often charged with the damage thus sustained by farmers, in addition to that really due to his burrowings.



FIG. 1.

Experiments performed in France to determine the usefulness of moles as insecticides show that the number of grubs, etc., destroyed by them is enormous. A single mole, in one instance, devoured 432 maggots and 350 grubs in four days. Another ate 872 maggots and 540 grubs in twelve days.

Prof. Weber, a distinguished naturalist of Zurich, Switzerland, performed some interesting experiments with moles to prove their carnivorous character and their destructiveness to larvae. In the stomachs of fifteen moles captured in different localities, not the slightest trace of vegetable matter could be found. He shut up two moles in a box in which fresh grass was growing, and also inclosed in the same box a case of grubs and earthworms. The moles devoured 341 white worms or grubs, 193 earth worms, 25 caterpillars, and a mouse—bones, skin, and all—in nine days. He next gave them raw meat cut in small pieces, and mixed with chopped vegetables. The moles ate the meat but did not touch the vegetables; and when vegetables alone were given them the animals soon died of starvation. It has been computed that a single mole may destroy 20,000 grubs in a single year.

In the face of these experiments it is positively asserted by some that moles will eat wheat grains with avidity, and that poisoned wheat introduced into their burrows through holes punched with a stick is sure death to them. We have tried the latter without impairing the health of the moles, and we have more faith in mole traps, in the use of which we have had considerable experience and with varying results.

We give herewith engravings illustrating two implements of destruction, both quite simple, either of which will be found practically useful.

The simplest form of trap, and one that will prove effectual if skillfully employed, is the jar mole trap shown in Fig. 1. A glass or stoneware jar is sunk into the ground under the run, as indicated in the engraving. The moles, while running along, fall into the jar, and the vertical slip-



FIG. 2.

pery sides of the jar prevent their getting out again. Field mice are also frequently caught in these traps, which leads to the suspicion that they are the authors of much of the mischief attributed to moles, whose burrows form convenient avenues for the intruders.

Another effective mole trap was described and illustrated in the *Rural New Yorker* some time ago, and not unlike one illustrated in these columns a few numbers back. It is shown in Fig. 2 and is thus described by our contemporary:

The spikes, A, three quarters of an inch wide and tapering somewhat at the end, are pressed into the ground beside the mole track as far as possible, so that the trigger, B, which is not yet attached to the lever, C, rests upon the surface of



the mole track, the prong head, D, meantime being held in its present position by the ring at the top of the upright square bar, F. Now let it slip from the hand. The force of the spring, E, will drive the prongs, D, into the ground, perhaps half way. Press them entirely down with the foot, and raise and lower them several times so as to give firmness to the earth and a free passage to the prongs. Then raise up the prong head to its present position, and place the lever, C, in one of the notches of the trigger, B, according as the other end of the latter is more or less depressed. Now the mole cannot again pass through this track without so pressing upon the earth as to move the trigger, at B, which releases the lever, C, and permits the spring, E, to act, sending the prong head down its place with great force, securely pinning generally killing the mole.

There are a number of other traps more or less effective, but the two represented in our illustrations exhibit the two diverse ways for catching moles, other appliances in use being simply modifications of the plans represented.

NEW SAFETY PULLEY.

The engraving represents an improved safety pulley applicable to cotton gins and other machinery, when it is desirable to be able to quickly arrest the motion of the machinery in case of accident. The device is very simple and not liable to accidental derangement. Fig. 1 in the engraving is a plan view of the device, and Fig. 2 shows the principal parts.

The pulley is loose on the shaft, and has attached to one end a slotted plate, A, near which the collar, B, is secured on the shaft. A collar, C, carries three pins, which fit corre-



McCORD'S SAFETY PULLEY.

sponding holes in the collar, B, and engage the slotted collar, A, attached to the end of the pulley. The pins projecting from collar, C, are kept into engagement with the collar, A, by a spiral spring surrounding the shaft and pressing against the collar, C. The latter is provided with a grooved base, which receives a forked arm attached to the lever, E, and the lever, E, is connected with a foot lever, D, so that when either lever is moved the pulley will be instantly disengaged from all connection with the shaft by the withdrawal of the pins from the slotted plate in the end of the pulley.

This device may be made double so that it may be made to shift from one pulley to another, and so reverse the machinery with which it is connected. It may be applied in this way to hoisting machines.

Further information in regard to this invention may be obtained by addressing Messrs. O. C. P. McCord and C. D. Churchill, of Hazel Grove, Independence County, Ark.

A Conductor's Printing Office.

It appears that German railway conductors are made happy by the addition to their equipment of a paper mill and printing office, the invention of a Berlin engineer, to be hung around the neck, which, according to an exchange, is to completely manufacture passenger tickets before the eyes of the wondering public. The apparatus is said to be somewhat complicated in construction, but its manipulation is as simple as its working is correct, for, should the operator not proceed in the way required by the mechanism, it will not print all the figures and words wanted, but the word "Falsch" (wrong) in the place where the fault was committed. At the same time this portable printer checks the number of tickets issued, so that any given moment the money in the hands of the conductor can be compared with the value of the tickets printed and taken.

Nervous Headache.

Dr. Glöckner, of Danzig, says, in *Allgemeine Medicinische Central Zeitung*, that he has found valicylate of sodium to be a remedy of great value in the treatment of nervous headache, especially if given in a dose of one gramme (gr. xv.) in the beginning of an attack. It usually produces drowsiness, and after a few hours the patient wakes up refreshed and free from pain. It, however, often fails to produce this effect in cases dependent on anemia.

THE ANTECEDENTS OF THE BELL TELEPHONE.

BY GEO. M. DODD.

Should the recent decision of the U. S. Circuit Court, at Boston, in reference to the Bell telephone patent, be sustained by the higher court, it will prove calamitous not only to inventors who have succeeded Bell in telephonic invention, but in the public at large, who will be at the mercy of a powerful monopoly, so far as telephonic communication is concerned. Already the workings of this power are beginning to manifest themselves in increased and apparently exorbitant rates, with no corresponding increase in the efficiency of the instrument or in the perfection of the service.

This being the condition of things, it behooves telephone inventors and telephone users to inquire as to the scope of Bell's patent, and to acquire a knowledge of the status of the art of telephony prior to the invention of Bell.

Should it be found that articulate speech had been transmitted from one point to another by means of electricity before Bell thought of the telephone, or should it be proved that instruments as old as the telegraph, without any alterations or additions whatever, could be made to transmit and receive articulate speech through the agency of electricity, then it might be very properly questioned whether the broad claim for the "new art of transmitting speech by electricity" could be sustained, even though Bell's results were secured by improved devices.

In regard to the early transmission of speech, it is certain that Reis, in 1861, transmitted vocal sounds by means of electricity, and it is authoritatively stated that he transmitted words.* It is certain that Reis's instrument can be used to transmit articulate speech; but now this instrument is claimed to be crude and imperfect. The ordinary Western Union telegraph key and sounder, as elements of a telephonic system, are even more crude and imperfect, and yet with a common telegraph key, used as a transmitter, I have transmitted articulate speech, which has been received by means of a common telegraph sounder, and this without modifying either key or sounder in the least. It is simply a matter of adjustment. Now, could a broad claim for talking to a telegraph key and listening to a telegraph sounder be sustained? Can a broad claim for a "new art of transmitting speech by electricity," by old and well known instrumentalities, be sustained, when the new results are secured by mechanical skill, exercised in adjustment merely?

Clearly, if Reis transmitted vocal sounds, or signals, or words, and if Bell has done the same thing through the agency of the same force, but in a more perfect manner, it should signify nothing, since degrees of perfection are not patentable. As a writer of this journal very aptly said a short time since: "If Reis's instrument was crude and imperfect, the same may be said of Bell's, for when it is constructed and operated according to his patent, and used independently of subsequent inventions, it proves inadequate for commercial purposes under the usual conditions of use." The original principle of the Bell telephone has really been replaced by Reis's invention, as will presently appear. That is, the Bell telephone has reached its present usefulness and popularity through the adoption of the Blake or some other form of transmitter substantially like the original Reis transmitter.

It is claimed by the advocates of the Bell system of telephony that the lack of efficiency in the Reis transmitter was due to the fact that intermittent currents of electricity were employed instead of an "undulatory" current, which Bell holds as essential; but it can be proved that in all contact telephone instruments the current is intermittent, and this is especially noticeable in the class having small contact surfaces like the Blake and Reis instruments.

If the language of the learned judges who rendered the decision above referred to is applicable to Bell's invention, it should also apply to that of Morse or Reis. The judge says: "There is some evidence that Bell's experiments with the instrument described in Fig. 7, before he took out his patent, were not entirely successful; but this is now immaterial; for it is proved that the instrument will do the work, whether the inventor knew it or not, and in the mode pointed out by the specification."

It is equally just to say that the telegraph key and sounder are operative for the transmission of speech, "and that it is immaterial whether Morse and other telegraph inventors knew it or not," for it is proved that the instrument will do the work, and as the invention of the telegraph now belongs to the public, every function of the telegraph instrument belongs to the public also.

It is even more just to say the same of Reis's invention. It makes no difference whether Reis knew it or not (but he did know it), the transmission of articulate speech by means of his instrument is an undebatable fact.

From the foregoing it will be seen that it is at least questionable whether any one is now entitled to a broad claim for transmitting speech by electricity.

Many of the claims of Bell as to the particular method and means employed by him for the transmission of telegraphic and other signals are manifestly too broad and cover some of the oldest inventions in telegraphy.




Fig. 2.—Oersted's Induction Apparatus.

For example, the first and second claims in his patent of March 7, 1876, read thus:

"1. A system of telegraphy in which the receiver is set in vibration by the employment of undulatory currents of electricity.

"2. The combination of a permanent magnet or other body capable of inductive action with a closed circuit," etc.

These claims are anticipated by the invention of Oersted in 1820 (Fig. 2). His apparatus consisted of a compound bar-magnet, H, mounted in a standard, I, and surrounded near its upper end with a coil, J. This coil was in a closed circuit with a distant coil, K, containing a vibratory magnetic needle. By moving the coil, J, up and down on the magnet, H, "undulatory" currents were produced, which vibrated the needle, giving intelligible telegraphic signals.

The more recent magneto-induction key of Siemens and Halske (Fig. 3) operates in substantially the same way.




Fig. 3.—Siemens and Halske's Magneto-Induction Key.

Between the poles of the magnet, L, is placed a Siemens armature, M, which, being vibrated by means of the lever, produces "undulatory" currents in the circuit in which it is included. This system antedates Bell's.

The first Bell telephone is shown in Fig. 4. The armature *r* is fastened loosely by one extremity to the uncovered leg of the electro-magnet *b*, and its other extremity is attached



Fig. 4.—Bell's First Telephone.

to the center of a stretched membrane *a*. When a sound is uttered in the larger cone *A* the membrane attached to it is set in vibration, and the armature connected with the membrane is forced to partake of the motion, and thus electrical undulations are created upon the circuit which influences the electro-magnet *f* at the opposite end of the line, so that the motions of the armature *A* and membrane *a* are the same as in the same members of the transmitting instrument.

Fig. 5 represents the later Bell telephone. The form is




Fig. 5.—Bell's Later Telephone.

simplified, but the principle upon which it operates is the same as that of the first instrument.

It will be observed that the transmitter and receiver are alike, that the instruments are upon a continuously closed circuit, and it seems to be questionable whether Bell's invention covers more than this specific arrangement.

But this arrangement is not the one so largely employed at present by our telephone exchanges. The instruments used at opposite ends of the telephone wires are incapable of being used interchangeably as transmitter and receiver. In the present system of telephony an instrument similar to that shown in Figs. 4 and 5 is used as a receiver, but employed in this way it is difficult to see how it differs materially from Reis's receiver, invented, used, and published twenty years ago.

The Reis receiver, shown in Fig. 6, is familiar to all



Fig. 6.—Reis's Receiver.

students of telephony, but the lack of patentable difference between it and the Bell instrument may not be apparent at first. In this instrument there are all of the essential elements of the Bell telephone—the magnet, the sounding board or diaphragm, and the armature, "capable of inductive action"—and while it can be used in its original form, as shown in Fig. 6, it may be simplified, whereupon the identical character of the instruments of Bell and Reis will at once appear.

The original Reis instrument (Fig. 6) consisted of an electro-




Fig. 1.—ORDINARY TELEGRAPH KEY AND SOUNDER EMPLOYED IN THE TRANSMISSION OF ARTICULATE SPEECH.

* *Berliner's Nachrichten*, No. 15; *Dingler's Polytechnic Journal*, vol. 169, p. 399, 1861.

magnet, A, mounted on a sounding board or diaphragm, B, and was provided with an armature, C, sustained by an arm, D, attached to the diaphragm. By dispensing with the adjusting screws and spring support of the armature (cutting them off on the dotted line in Fig. 6), and by attaching the armature directly to the angled arm, D, as in Fig. 7, an operative instrument is formed, which, although simpler than the original instrument, possesses no patentable features.

By straightening the angled arm, D, so that the diaphragm may be placed directly in front of the poles of the magnet, as in Fig. 8, the form of the instrument is further changed, but it is substantially the same as the original. Leaving out the arm, D, and attaching the armature, C, directly to the diaphragm, B, is not an invention, and the instrument is still the Reis receiver.




Fig. 7.



Fig. 8.

Suppose the armature, C, to be flattened or rolled out so as to be capable of replacing the diaphragm, B, the instrument would then appear with but two of the original elements (Fig. 10) viz: the magnet, A, and the armature-diaphragm, C: it is still essentially the Reis receiver. Is it supposable that a valid patent can be obtained by omitting a few non-essential elements from the original instrument?

Reis's receiver was used in connection with a transmitter of his own invention, which was totally different from his receiver. The transmitter (Fig. 11) consisted of a box pro-




Fig. 11.—Reis's Transmitter.

vided with a mouthpiece, and covered by a membrane, E, carrying a platinum contact surface, F, which is touched lightly by a platinum point carried by the arm, G, one end of the latter resting in the mercury cup to make a perfect yet frictionless electrical connection. The platinum, F, and arm, G, are in the circuit with the battery and receiver, and the interruptions of the current take place between the platinum point on the arm, G, and the platinum, F, carried by the diaphragm.

Fig. 12 shows the essential members of the Blake trans-




Fig. 12.—Blake Transmitter.

mitter, which is now used almost exclusively. It is hardly necessary to point out the similarity between this instrument and the one just described. The diaphragm, E, platinum contact, F, and spring arm, G, are substantially the same as the elements E, F, and G of the Reis instrument, the only difference being the substitution of a piece of carbon in the end of the arm, G, for the platinum in the end of the arm, G.

From what has been said it will be seen that the system of telephonic communication in use to-day is more Reis's than Bell's.

An Agricultural and Industrial Exhibition is to open on the 14th of September, 1881, at the exhibition grounds, Mile-End, Montreal. The prize list fills a pamphlet of 200 pages. Twenty-five thousand dollars in prizes are to be distributed to exhibitors. It closes on the 23d of the same month.

LIEBIG'S EXTRACT OF MEAT.

Baron von Liebig, Germany's great chemist, ascertained that the soluble constituents of 34 pounds of pure muscle meat (equal to 45 pounds of ordinary meat as it is received from the butcher) may be concentrated by boiling to 1 pound of extract, sufficient for the preparation of 100 parts of bouillon. With his keen perception he foresaw that the manufacture of this extract might become a great industry. He conceived the idea that the transmarine countries rich in cattle might become tributary to the necessities of Europe.

In the year 1850, at the beginning of the manufacture, the Royal Apothecary at Munich consumed scarcely one hundredweight annually, that is, one-tenth part of an ox, and Liebig himself did not imagine that in a score of years the number of cattle falling victims to this industry would number millions. This statement will not appear exaggerated when it is considered that in the summer season there are led daily to the slaughtering bench from one thousand to twelve hundred oxen.

The manufactory of Liebig's Extract of Meat Company lies on the eastern (left) shore of the Uruguay River in that state, and is as important to Fray Bentos as Krupp's great steel manufactory is to Essen.

Proceeding systematically, we should consider first the immense pasturing lands upon which the cattle peacefully graze. These cattle are children of the Pampas, descendants of the European cattle introduced by the Spanish conquerors. The large level pastures were especially suited to them, and here they increased greatly and now rove in innumerable herds.

For the manufacture of the extract the best pieces of meat are selected, for the simple reason that these pieces are the most profitable for the extract. When the animals are driven in from the Pampas to Fray Bentos they are kept for a week upon the pasturing places mentioned, where they are permitted to rest and feed. Then they are driven to the corrals, great inclosures capable of containing five thousand oxen; from here men mounted on horseback, swinging their lassos, drive the cattle by degrees into other smaller corrals, until finally the way is so narrow that the animals can only proceed one behind the other. A man stands at the side upon a staging with a short knife. With unerring certainty he strikes the animal close behind the horns into the spinal marrow. As if struck by lightning the animal falls dead upon a platform which rests upon wheels. The body rolls upon a track to the slaughtering house, where with almost incredible celerity it is skinned and cut in pieces by skilled and practiced men. In less than seven minutes a whole ox is cut up. In the slaughtering season over five hundred men are employed, powerful fellows, who are very good hearted and harmless characters in spite of their bloody occupation, and notwithstanding the fact that their nourishment consists almost exclusively of meat. The dexterity with which they handle the knife excites astonishment. The meat is separated from the bones, as if the knife were guided through soft butter. One hundred and fifty to two hundred oxen can be handled in this way per hour.

The greatest cleanliness prevails. A plentiful supply of water is obtained from the river for washing. The slaughter house is roofed with iron and glass, and a railway connects it with the principal buildings of the establishment.

The raw material is conveyed in various ways from the slaughter house. The hides are salted, the horns stored, and the tongues are cooked and preserved in tin cans. The best pieces, as free from fat as possible, are used for the manufacture of the extract, while the inferior pieces are made into *tasajo* (meat salted and then dried in the air), which is a favorite article of food for the black population of Brazil and the West Indies. The fatty parts furnish material for the large tallow buying houses. The refuse and offal are dried and made into fertilizers.

The meat for the manufacture of the concentrated extract is freed from fat and gelatine, and passes through the following processes:

First it passes through four cutting machines, which discharge it into nine large wrought iron tubs, each one holding five thousand kilogrammes. In these the meat with an equal weight of water is heated to boiling. Then the liquid passes through pipes into an apparatus invented by Prof. Max Pettenkofer, where it is clarified and separated from the fatty part. Air pumps carry the remaining fluid mass into two reservoirs placed seven meters higher, from which it passes into the evaporating apparatus after it has gone through several straining processes.

The evaporating is effected in five large reservoirs, each having a hundred disks of the same material, which revolve in the liquid; then the extract remains quiet in other reservoirs until the next morning, when it is placed in two cast iron kettles surrounded by hot water jackets, each containing 10,000 liters of the extract, where it is reduced to a uniform mass. Then samples are taken which are subjected to the careful tests of the chemist of the establishment. If these turn out to be perfectly satisfactory as to purity, aroma, and consistency, the extract is packed in tin chests, each containing one hundred pounds, and sent to Europe. Packing the extract in small stone jars for the retail trade is done at the general depot in Antwerp.

The cooked meat remaining in the kettle is dried in the air, and with the addition of a few nutritive salts, and after being ground, is manufactured into the so-called meat-food meal.

Connected with the establishment are tin, locksmith, and

joiner shops, a foundry, pump works, steam cranes, etc. The company import coal from England at a great cost, from 7,000 to 8,000 tons being consumed yearly.

Four thousand tons of salt are consumed yearly for salting the hides and *tasajo*.

The cattle slaughtered for the extract are at least four years old, as younger animals will not supply a strong extract.

It is unnecessary to speak of the great value and extensive use of the extract, as it is everywhere acknowledged to be a standard article.

ENGINEERING INVENTIONS.

An improved car axle box has been patented by Mr. Wm. Ham H. Taylor, of Richmond, Va. The object of this invention is to prevent journals of car axles from heating, and thus avoid the risk of danger and injury resulting from hot boxes on railroad trains. For this purpose the inventor provides for retaining water in contact with the box on one or more slides to dissipate the heat arising from friction.

An improved elevated railway has been patented by Mr. John G. Curtis, of Ludlow, Pa. The invention is more particularly intended for use inside of a building, to convey goods from one part of the building to another, and it may also be used for conveying goods from one building to another, or from place to place in a tannery or other extensive establishments. It consists in a novel construction, arrangement, and combination of an elevated rail or track, a two-wheeled truck, and a car or platform suspended from the truck.

Messrs. James F. Guild, of Dundee, County of Forfar, Scotland, and Arthur E. Knights, of New York city, have patented an improved steam steering apparatus. The objects of this invention are to move a vessel's rudder easily, quickly, and with perfect regularity, to have it completely under control and almost silent in its action, thus in a great measure overcoming objections to the usual steam steering apparatus, especially on passenger steamers; also to provide for steering vessels either by hand or power; to provide for the relief of the operative mechanism from the injurious effects of shocks by strokes of waves against the rudder, and to reduce the power usually required in apparatus of this character.

Messrs. John H. Reynolds, of Emerson, Iowa, Elisha P. Reynolds, of Rock Island, Ill., and Ben Reynolds, of La Mine, Mo., have patented an improved self-dumping trap which automatically discharges its load of earth or other material into any receptacle below its dumping platform on the release of gripping irons by the operation of a conveniently placed hand lever. The invention consists in supporting one or more pivoted dumping platforms, in an elevated framework, said framework supporting the upper end of "ramps" or inclined approaches thereto, whereon teams drawing loaded vehicles may ascend to the platforms to deposit their load of earth or other material thereon and descend therefrom.

An improved baling press has been patented by John Brown, of Memphis, Tenn. The object of this invention is to improve the construction of the baling presses for which letters patent No. 230,216 were granted to the same inventor October 7, 1879, to adapt them to be operated by steam power, and to make them more convenient in use.

The Presidential Cold Air Machine.

The apparatus which proved most satisfactory in cooling the chamber of the wounded President was furnished by a Mr. Jennings, of Baltimore. It was devised for use in a new process of refining lard. According to the inventor's description the apparatus consists of a cast iron chamber, about ten feet long and three wide and three high, filled with vertical iron frames covered with cotton terry or Turkish toweling. These screens are placed half an inch apart, and represent some three thousand feet of cooling surface. Immediately over these vertical screens is placed a coil of inch iron pipe, the lower side of which is filled with fine perforations. Into a galvanized iron tank, holding 100 gallons of water, is put finely granulated or shaved ice (and salt when a low temperature is required). This water is sprayed upon the sheets in the lower tank constantly. In each end of the iron chamber are openings thirteen inches square. To the outer end of this chamber is a pipe connecting with an outdoor air conductor. To the opposite end is connected a similar pipe leading into an ice chamber at its top, and from the bottom of the same a pipe leads to a small exhaust fan, and from the fan the now cold and dry air is forced direct into the President's room through a flue some twenty feet in length. Air at 90 degrees temperature to day is supplied at the rate of 22,000 cubic feet per hour at the register in the President's room at 54 degrees, and with the windows and doors open the temperature at the President's bed (twenty-five feet away) is maintained steadily at 75 degrees day and night. When the cold air machine was introduced it was intended to keep the windows and doors closed, and under these conditions the machine would create and maintain a temperature of 60 degrees in the hottest weather without using the auxiliary ice-chamber now used, which was the suggestion of Professor Newcomb and Major Powell, to meet the requirements of cooling the room with the doors and windows open. The closing of them gave the room an air of gloom. An extra ice chamber fan and engine has been put up in a room opening into the hall near the first apparatus, to be used in case of accident and to cool the corridors of rooms adjoining the President's.

STEAM BOILER NOTES.

The reports of the chief engineers of the English boiler insurance companies of Manchester have been published and contain much useful information for steam users. Mr. McDougall, of the Boiler Insurance and Steam Power Company, claims to have made 13,971 thorough internal examinations and hydraulic tests, and to have had not one explosion and but one serious collapse among the 20,000 boilers in his care. The passage of the Employers' Liability Act, he thinks, will greatly extend the operations of boiler insurance companies, and should tend to effect a great improvement. Mr. Livingston E. Fletcher, chief engineer of the Manchester Steam Users' Association, in his monthly report, states that 971 boilers were examined from May 28 to June 24, of which 467 were thorough annual inspections.

The discussion of the subject of flat cast iron boiler heads is still going on in Philadelphia, and the interest seems to increase. The *Iron Age*, possibly speaking by authority, repeats the assertion that "the Hartford Company have instructed their agents in Philadelphia not to approve boilers with flat cast iron heads with a greater diameter than 36 inches," but says, "the company do not wish this action to be construed as indicating a desire not to accommodate manufacturers; but in view of the recent verdict of the coroner's jury, in the case of the explosion at the dye works of Gaffney & Dolan, they do not care to continue writing on this class of boilers."

Since the experimental bursting of a duplicate of the Gaffney boiler head by the makers, Sidebotham & Powell, on the 13th of July, as suggested in our "Notes" of July 2, to the jury, and illustrated in the *Scientific American* of July 30, the inspectors of Philadelphia seem to have plucked up courage, especially the city inspector, Mr. Overn, who has been prompted by a lawyer, the city solicitor, to stand on his dignity as a mechanical expert, and he accordingly appears, by the *Ledger*, to say that he regarded the test as a satisfactory test as to the strength of cast iron in the ends of the boiler. The cast iron held good up to 450 pounds, and under this showing he (Overn) would have no hesitation in giving a boiler, with the same quality of cast iron, a pressure of 80 pounds to the square inch.

It is due to this gentleman to say that this is perfectly in accordance with his faith before the Gaffney explosion, but a misinterpretation of the cause of that accident by some experts shook his faith in his own judgment.

Some instances of apparent hardship to owners of steam boilers since the flat head controversy began are given in the *Philadelphia Record* of the 16th of July. The lumber mills of Van Horn & Son, at Whitehall, have been closed since the 11th inst., and are likely to remain so, waiting a city inspector's certificate. The machinery of this firm had been running night and day to fill orders, and the loss, besides the cost of new boilers, is represented as being heavy. Cause, 30 inch flat cast iron heads in their 42 foot boilers. Borle & Mackay, Frankford, have received similar treatment from one set of inspectors, while the other passed them so they could continue work. A large number of other boilers have lately been refused certificates, and when this is done by the city inspector they must stop. Messrs. Garard & Co., large manufacturers of cotton yarns, in Frankford, were compelled to throw out four boilers 80 feet long, while 40 feet of the furnace end of them that were removed fourteen years ago are said to be running now under inspection. It may be urged by the inspectors that these 80-foot boilers are dangerously long, but they have an exceptionally good arrangement of supports, which has served for over thirty years to prevent undue strains from sagging. They rest at the ends upon solid supports. Two sets of four volute steel car springs are placed upon heavy arched girders, at 88, that span the boiler settings at such intervals as to make even and elastic supports, thereby preventing undue strains on the lower side of the boiler from slender proportions.

These four boilers were built by Brooks and Stanhope, in 1850, John Powell (now of Sidebotham & Powell) foreman, and for many years after they were put to work the engineer used leaden gaskets for the man hole joints, and he had a habit of adjusting his plate and gasket when closing the boilers and screwing up pretty hard. But if the joint was not tight after raising steam, he was accustomed to beat the head with a heavy sledge near the gasket seat, to settle the uneven plate upon the lead and make it steam-tight. The marks of this violence are still plainly seen on the castings, which are about the same thickness and style as the Gaffney boiler heads.

The *Ledger* also credits Mr. Overn with the remark "that he was inclined to believe, from what he had recently observed, that eventually the city would have the entire work of inspection, for he thought the Hartford people would drop the inspection department of their business and confine themselves solely to insurance, relying on the city's inspection."

It naturally occurs to lookers on who feel an interest in the subject to inquire why the verdict of an unfriendly jury should make a breach between an insurance company who have heretofore been not only willing but desirous of insuring, and the friendly manufacturers who were willing and desirous of having their insure boilers that have during their experience proved as safe as any of that type. The *Philadelphia Record*, in commenting on the flat head matter and its effect on the manufacturing interests since the Gaffney explosion, says: "Nearly two-thirds of the boilers in use in the suburbs have flat cast iron heads, and

the owners are in daily fear that an edict will be promulgated which will put a temporary stop to their operations."

We learn that a boiler explosion took place about the 19th of July, 1881, at Watertown, near Marietta, Ohio. The boiler of a saw mill was blown to atoms. Hiram Brockway and Eugene Barclay were instantly killed. Three others, Isaac Johnson, Robert Alexander, and William Connor, were fatally injured. Johnson has since died.

The June number of the Hartford Steam Boiler Insurance Company's circular contains the Inspector's report for April, 1881, by which it appears that 8,000 boilers were viewed, of which 1,593 were inspected internally and externally, and 328 dangerous defects were found; notable among them were 23 safety valves in dangerous condition, and 74 boilers without steam gauges. 39 boilers were condemned in April. There is also notice of 8 explosions in May, and one illustrated explosion that occurred in 1877, in Brooklyn, N. Y.

MISCELLANEOUS INVENTIONS.

Mr. William A. Thompson, of Brooklyn, N. Y., has patented an improved fire escape, which consists of a cradle formed of curved side bars connected by cross bars and provided with supporting bars or legs, the cradle being hinged to a rod attached to the window casing below the sill, and having a ladder attached to its free end and provided with means whereby the fire escape can be extended from the window when required for use, and folded down inside the window when not required for use.

An improved baling press has been patented by Mr. Nelson Arave, of Hooper, Utah Ter. The object of this invention is to press hay and other materials in successive bales by the continuous forward movement of the driving mechanism.

Heretofore alloys in which lead forms a component part have been used for coating cast and wrought iron to protect the same against oxidation, and zinc and tin alone are in common use for this purpose; but several objections and difficulties attended the use of these materials when applied by the methods now known—as, for instance, when zinc or tin is used and applied directly upon the iron the zinc attacks the iron in such manner as to injure its durability and tenacity, and this is also true of such alloys as antimony, bismuth, and lead, and nickel, tin, zinc, and lead, and, besides, in applying these alloys or the zinc a dross is formed in the molten bath, which is troublesome to remove, and results in a loss of metal, and wrought or cast iron has never been successfully coated with unalloyed lead. Mr. William Frishmuth, of Philadelphia, Pa., has patented a process of thoroughly and effectively coating cast iron or sheets of wrought or cast iron or other metals with pure lead, or with zinc or tin, in such manner that the metal coated will be protected against oxidation and its durability and tenacity preserved, and in such manner that there will be no formation of dross in the molten baths. The invention consists essentially in protecting or preparing the surfaces to be coated by depositing upon them, by electroplating or otherwise, a thin coating of nickel, or an alloy of nickel and aluminum.

It is well known to workers of gold and silver ores that the pan amalgamation process always results in a very considerable loss of the precious metals and of the quicksilver, the loss of the former being in a great measure due to the fact that the particles of metal are coated with some substance that repels the quicksilver or prevents its contact with the metal, and the loss of the quicksilver being principally due to the "flouring" of the latter, because of its trituration in the pans and because of the presence of certain interfering mineral substances that coat the globules of quicksilver and prevent their reunion. Messrs. William H. C. Mathews, Charles W. Ayres, and Madison D. Campbell, of Bodie, Cal., have patented a cheap and effective compound to be used for preventing this loss of both the gold and silver and the quicksilver, by brightening the particles of the precious metals and by preventing the coating of the quicksilver globules.

An improved apparatus for separating sulphurets in ore washing has been patented by Mr. William F. Devan, of Gwin Mine, Cal. The object of this invention is to improve ore washers and save the sulphurets by an operation that is both continuous and economical.

An improved bird cage has been patented by Mr. John H. Abernathy, of Covington, Ky. The object of this invention is to protect the animals confined in cages from suffering by external violence and from being preyed upon by larger animals.

An improved adjustable piston, which is so constructed that the packing of the same can be depressed and spread proportionately as it wears off, by adjusting the piston accordingly, so that the packing will always fit closely in the pump-cylinder, has been patented by Mr. James Preston, of New York City. A packing of any desired size is held between the opposite convex or flat conical surfaces of the plates, and in case this packing becomes worn off it can be spread by forcing the disks toward each other.

The Eyes of Science.

In a communication in the *Herald*, describing the wonders of the eyes which science has fashioned—telescopic, microscopic, spectroscopic, and, most marvelous of all, photographic eyes—Mr. Richard H. Prier says:

Ordinary human eyesight, even when strengthened and extended by optical devices, possesses certain imperfections and is used under certain difficulties. For instance, at least a tenth of a second is required for the eye to take a

full look at any object. Even if the eye could see an object in less time the image remains at least this time impressed on the retina. Thus the eye cannot see an object which moves very rapidly, and even when an eye sees an object moving not too rapidly, or moving in a circle so as continually to renew the impression (as where a burning rod is whirled round in a dark room), the object is not seen as it really is, but the successive images, owing to the persistence of luminous impressions, are blurred together into an image utterly unlike the real object. Again, when an object is rapidly changing in shape the eye is often quite unable to send distinctly any one of the shapes which the object assumes. Thus scarcely one of the attitudes of a galloping horse can be seen by the human eye, inasmuch that the finest pictures of a charge or a race show not one attitude which a horse really assumes when galloping. Yet again, the eye is often prevented from recognizing the true shape of an object which is itself at rest, by reason of continual fluctuations in the medium through which the object is seen, as for instance when the telescopic image of a sun spot is examined through disturbed air, or when smaller details of the solar surface are examined through the air at its very stillness.

OPTICAL DIFFICULTIES.

In all these cases the real trouble is that the eye requires a certain definite though short time in which to take in, as it were, the visual image, and that during this time the object forming the image is changing in form, either actually or apparently. On the other hand, there are cases of an opposite kind, in which the eye fails to recognize objects or their details because of their exceeding faintness, the eye gaining nothing by the length of time during which it is in action. Thus if we look at a point in the heavens at night where there is a telescope star the eye fails to see that orb if directed toward it during the tenth of a second (the period necessary for distinct vision under ordinary conditions), nor can the eye see the orb better if directed toward it for a second or for a minute or for an hour. Now science possesses an eye free from these defects, by means of which ordinary vision may be made to see an object as it would be seen if the human eye could take in the image in the thousandth part of a second, or even less time, or, on the other hand, as it might be seen if the human eye could look steadily for an hour or more, gaining distinctness of vision precisely in proportion to the increase of the time during which the eye was used.

A LIGHTNING GLANCE.

For instance, in lecturing on the sun I have been able to tell my hearers that a certain photograph of the sun's surface had been so rapidly taken as to show details which no astronomer had ever actually seen or could see, even though he used the most powerful telescope ever made, and gave to the study of the sun with such an instrument every moment of his working life.

A LONG GAZE.

On the other hand, but a few weeks ago I was looking in Dr. Henry Draper's observatory at a picture of the great nebula in Orion which had been two hours and twenty minutes forming itself on the retina of the photographic eye of science—in other words, the negative had required an exposure of this duration. I say nothing, though I might well say much, on the mechanical skill and ingenuity required to retain the telescopic image so long unchanged in position, though all the time the diurnal motion of the heavens was carrying Orion round the heavens at the rate in reality a slightly greater rate at which the sun moves in the skies, nor do I dwell on the optical and physical difficulties involved in the task which Dr. Draper had thus successfully achieved. The point I wish chiefly to dwell upon is this, that where such a photograph is taken science does in reality employ an eye which can give hours to a single look. And let it be noted that we see now but the beginning of the use of the photographic eye, which can see in the five-thousandth part of a second if need be, or if need be can rest its gaze for many hours on the same object, seeing more and more as minute after minute passes on. Yet already the swifter view of the photographic eye has shown details which the unaided human eye, or that eye aided only by the telescope or microscope, could never see, while the steadfast gaze of the photographic eye has revealed what it has been given to no human eye to see by direct vision.

SEES AND DELINEATES.

Note, further, that the photographic eye in seeing, delineates also, whereas often enough the eye keener to see is but little skilled to guide the hand to delineate what it sees, and yet oftener the ordinary eye can obtain but so brief a view of an object that there is no time to draw what is seen with but fainting to memory, which is such matter is too often treacherous. The most pictures of the solar face given as drawn by any human artist has much less value than have Messrs. Draper's instantaneous photographs of the sun's surface. The best picture of the great Orion nebula—which, despite Mr. Draper's opinion in favor of the one taken with Lord Rosse's telescope, I consider to be unquestionably Mr. Trouvelot's picture taken with the great Washington telescope—shows no details which are not clearly recognizable in Dr. Draper's beautiful negative, while skillful though Mr. Trouvelot is as an artist, nature has surpassed him in presenting truthfully not only all details but all grades and varieties of shading. And these are but illustrative instances, being but a few, of the beginning of the application of photography to science.

IMPROVED CAR STARTER.

No subject is more deserving of the attention of inventors than that of starting our heavily laden street cars after they have come to a full stop, and singularly enough no subject has been more bunglingly treated. The two essential qualities of a car starter are simplicity and durability. Complicated and expensive mechanism for this purpose is entirely out of the question, as no class of devices are subjected to greater wear or greater inequalities of strain.

The car starter shown in our engraving happily combines all the essential qualities, and has proved itself by actual and continued use to be adequate to all the requirements of a device of this character. The clutch employed is of novel construction, and the leverage is equal to the radius of the wheels.

In the engraving Fig. 1 is an elevation of a portion of a car, showing the clutch of the starter in section. Fig. 2 is an inverted plan view. Fig. 3 is a perspective view of the clutch and clutch lever, and Fig. 4 shows the inner end of the clutch lever.

The axle, A, with which the apparatus is connected, has attached to it a sleeve, B, and a clutch, C, which may be rotated around the enlarged central portion of the sleeve.

In connection with this clutch there is a lever, D, the central pivoted end of which is pivoted in a slot in the clutch, C, in such a way as to have freedom of motion to a certain extent up and down. Upon the outside of this central portion are winged flanges which embrace the sides of the clutch, C. A pivotal pin, passing through these wings as well as the central portion, and clutch, C, give steadiness to the lever, D, and prevent it from lateral movements. At the extreme inner end of the lever, D, there is a recess, of a semi-globular form, elongated in the direction of the length of the lever. A ball, E, having freedom of movement, is placed between this recess and groove, around the central portion of the sleeve, B. This ball, in the movement of the lever at the proper point, is clamped against the groove, and, having freedom of movement in its own recess, presents continually a new wearing surface, and avoids the inconvenience and bad results which would follow if no such ball were employed.

By reason of the longitudinal form of the recess, the ball, in the upward movement of the lever, is brought into engagement in the upper part of its recess with the groove in the sleeve, and therefore the resistance of the ball, being in a slightly angular direction, is increased to such an extent that it never slips.

The outer end of the lever, D, is slotted to receive the link of the chain, E, which is held by a bolt, so that if it is necessary to shorten the chain at any time the bolt may be withdrawn, and then replaced through another link of the same chain. The chain, E, passes over a pulley secured to the bottom of the car, is attached to a rod, F, which, in turn, is attached to the draw bar, G, by a pivotal connection. The inner end of the draw bar connects with one end of the lever, D, pivoted to the bottom of the car, and a spring, with this lever between its pivotal point and its free end, presses it back, and draws back the draw bar, and holds it in this position when no force is applied to it.

It will be seen that with any forward motion of the draw bar the lever, D, will be raised, and the power for the moment will be exerted to great advantage, and the car will be started easily without strains or shocks on the horses, harness, or car.


To check any retrograde movement of the car upon up grades, an auxiliary ball, H, is placed in a cavity in the clutch, C. When the car makes the slightest movement backward the ball, H, wedges in the cavity and stops the car.

The starter is not intended to supersede the brakes, but to be used as supplementary to them. The main object is to lessen the labor of overcoming the inertia at the initial of the forward movement, and also to equalize the draught after the loaded car has been put in motion.

There is also an attachment by which the driver is enabled to reverse his car by throwing the lever out of gear—and preventing the locking of the wheel—simply by a pressure of the foot. If


by any neglect on his part he should fail to put it in gear again, it acts automatically as soon as he attaches the horses to the draught bar.

The ball of the checking device is thrown out of position to engage the clutch by means of a rod attached to the yoke, H, and extending into the ball cavity. This yoke is operated by a pedal, I, through the medium of the angled levers, K, L, the rod, J, and a short section of chain connecting the double arm of the lever, I, with the yoke, H. By means of this mechanism the checking device may at any time be thrown out by the pressure of the foot on the pedal, I, and should it be desirable to keep it out of engagement with the clutch, the catch on the pedal is hooked under a plate in the platform.



IMPROVED DROP PRESS.

rated by a pedal, I, through the medium of the angled levers, K, L, the rod, J, and a short section of chain connecting the double arm of the lever, I, with the yoke, H. By means of this mechanism the checking device may at any time be thrown out by the pressure of the foot on the pedal, I, and should it be desirable to keep it out of engagement with the clutch, the catch on the pedal is hooked under a plate in the platform.



HILL'S CAR STARTER.

One of the great advantages gained is that it removes the concussion from the car, preventing the sudden jerking of passengers inside when the car starts up. So smoothly does it start that even a lady could get on at the time without inconvenience. Another advantage is that passengers standing up are not jostled and thrown around the car, as all the jerking and pitching is done away with. The explanation of the matter is simply that it moves the car to move the load, instead of moving the load to move the car.

This improved car starter is in continuous use on some of our leading horse-car lines in this city, giving great satisfaction. This starter has been applied to some of the car lines in Baltimore with great success, and it should meet the approval of all street railroad companies.

Further information in regard to this useful invention may be obtained by addressing P. B. Shaw, Grand Hotel, 31st street and Broadway, New York city, or the American Car Starter Co., Williamsport, Pa.

NEW DROP PRESS.

The variety of work that can be welded and forged under a drop press, and the great economy and rapidity with which it can be done, have worked a complete revolution in the production of steel and iron shapes. In no other way can duplicates be made so surely to replace missing or broken parts.

We illustrate a new drop press which is a great improvement over those now in use. The patent connection between the crank pin and hammer is slightly elastic and acts as a cushion.

The right tension can be much easier attained and changes can be more readily made than with the strap in common use. Its first cost is low, and when worn out can be quickly replaced at a small expense. We are informed that quite a demand has arisen for this connection to replace old straps on lifters of drop presses of other manufacturers.

Internal steel ratchets—whose teeth are much stronger than those of external ratchets—are used in constructing this press, and the ratchet being attached to the rim of the main driving gear the transmission of the strain through the arms of the gear wheel is avoided. The greatest strain on crank and ratchet drop presses comes when the dog fails to catch a tooth at its furthest rebound, then it falls back to the next tooth. This ratchet contains forty-five teeth, and hence the falling back in this machine is always through a very small distance. This press is manufactured by Williams, White & Co., Moline, Ill.

Stream Wagons.

The Colusa Sun says: "After all his experiments, Captain Roberts, of the San Joaquin Company, is still an enthusiast about his stream wagon enterprise. We had a conversation with him some time ago, and he thinks that roads suitable for his wagon can be built very cheaply. While the wagons run and pull very heavy loads on common roads, he thinks of digging two small graded ditches and filling with gravel, which will pack as hard as iron, and give a solid road for each of the broad wheels, and for the wagon wheels that follow with the loads. The Chico Enterprise, of Tuesday, has an item to the effect that this 'stream wagon' has been thoroughly overhauled and improved at the Union Iron Works, Sacramento, and on a recent trial worked satisfactorily. Its weight is 17 or 18 tons, and it is calculated to haul 50 tons of grain at each trip. It will be taken to the Upper Sacramento valley in a day or two, and will engage in grain hauling between Riceville and McIntosh's Landing."

"Capt. Roberts will, if this one shall prove the success he anticipates, put on wagons to run to all the principal landings on the river, and thus cross-section the entire Sacramento valley. He will have, in effect, a freight railroad across the valley, from foothill to river, every eight or ten miles. We sincerely hope that the wagons may prove successful, as it would be one of the grandest things for the Sacramento valley that could be imagined; that is, always provided we can keep the river navigation from being destroyed."

SHELTERING HAY RICK

A straw or hay rick that can be used as a shelter for cattle, horses, etc., is shown in the annexed engraving. The frame of the stack consists of two square fences with a passage way between them. The passage is covered by a peak roof framed or tied, the rafters being formed of fence rails or thick poles, with their lower ends set a small distance in the ground. The hay is placed in the spaces inclosed by the fences and upon the rafters, and the stack is built up to the ordinary height. Very long stacks can be provided with two passage ways if desired. It is considered advisable to construct the frames of these hay stacks as permanent structures.

Pharaoh's Serpent and the "Sea Snake."

We have heard a good deal about the amusing chemical toy "Pharaoh's serpent," both harmless and injurious, from its unhealthy vapors given off in the process of burning, but little about another very ingenious and singular chemical phenomenon, discovered and exhibited by the late Prof. Graham, Master of the Mint, which might be termed, in contradistinction to Pharaoh's land serpent, the "sea snake," as it is produced under water. His experiment went to show the prodigious amount to which the metal palladium will absorb hydrogen: an amount exceeding by some hundreds of times its own bulk. Two ribbons of palladium, attached to the two poles of a battery, were seen loosely coiled in a water bath. The current was turned on; the ribbons took in so much hydrogen that they expanded, uncoiled, and stretched themselves across the bath, as if alive. The current was reversed, the hydrogen was thrown off, and the ribbons resumed their coil. They might have been compared to a couple of writhing worms. The sight was amusing; but it exemplified the researches by which Prof. Graham has thrown light on an important question in chemical science, and led him to the discovery of the metal to which he has given the name of "hydrogenium." "What do you think," wrote the Professor to Hofmann, "of a metallic hydrogen, a white magnetic metal?" The condensation of hydrogen in palladium, and the discovery of the occlusion of hydrogen in meteoric iron, confirmed the conclusion to which spectrum analysis had previously conducted us, that the meteorites come from an atmosphere of incandescent hydrogen existing under very considerable pressure. Graham's fame as one of England's greatest chemists justly rests upon this important discovery.—*Monthly Magazine*.

THE SEA LAMPREY.

The lampreys form a small group of hardly more than a dozen varieties, and are the most imperfectly developed, and occupy the lowest grade of all fishes, with the exception of the Lancelot. Their skeleton consists entirely of cartilaginous material. They are destitute of ribs, shoulder girdle, real jaws, and scales, and are possessed of only one nostril, and their gills have the form of fixed sacs. In their habit of feeding and attaching themselves to the bodies of other fish, from which they rasp off the flesh and suck the juices, they become very suggestive of the leech.

The body of the sea lamprey is olive-green, mottled with dark brown. Length from two to three feet; numerous rows of mucous ducts on the head and body. The mouth, when not attached to any object, forms a longitudinal fissure; when attached it is circular in form. The teeth are of various kinds, generally disposed in concentric circles. In the throat, and partially closing it, is a group of three large teeth. (See illustration.) Lips fleshy, with a distinct and slightly fishbristled membrane, and beneath a deep triangular fossa, having a fold on each side.

Lampreys are frequently found attached to sturgeons, from which they suck the slime and mucus exuded in abundance through the pores of the sturgeon. All the skate family provide favorite food for the lampreys, in whose bodies they rasp out deep wounds, which

often produce ulcerations. The young pass through several changes before becoming perfect lampreys. At first the young are destitute of teeth and have only rudimentary eyes.

With the Italians and French the lamprey is considered a great delicacy, whereas in England only the poorer classes eat it. In this country it is valued only by a few epicures,

lamprey will receive special attention from the French cooks, and is to be served in every known style.

The negroes of the South have great respect for the lamprey eel on account of its supposed medicinal qualities, the skins being in great demand as infallible cures for rheumatism and kindred ailments. The skins are bound about the ankles, wrists, and neck of the patient while fresh from the body of the eel, and are worn for long periods of time, in fact often till they drop off.

In the months of March and April the lampreys begin ascending our fresh water rivers and streams that empty into salt water. Here they construct what might be called a nest, composed of stones piled up in a heap. These stones are carried from a distance by means of their sucking mouth. In these conical heaps of stones they deposit their spawn.

Botanical Sources of Tonga.

Some time ago a native medicine called "tonga" was introduced into England and the United States from the Fiji Islands, where it has long been in use as a remedy in neuralgic affections. No clue to the origin of this drug, which belongs to the vegetable kingdom, has hitherto been obtained, as the natives have jealously guarded the secret. According to a recent number of the *Gardener's Chronicle*, however, the botanical source of the medicine has now been found out through specimens sent by Mr. R. L. Holmes, and submitted to Baron Von Mueller for identification.

The component parts of tonga consist of two plants only. The first, called by the natives "Aro," is *Premna lutea*, and belongs to the order verbenaceae. Mr. Holmes states that it is, in open dry places, a shrub,

flowering when quite small, but near water-courses becomes a tall tree, the timber of which is used in building, the inner bark being the part used in medicine. The other plant, known as "Nai Yalu," or "Watu," is an Arad, the *Raphanophora ciliensis* of Seemann. It is a creeper, growing freely in sheltered places, climbing over stones and the like till it finds a tree, when it changes its nature. From a small vine, not thicker than a quill at the foot of a tree, it gradually expands, the stem growing to one or two inches in diameter, and the leaves, as many feet long, become pinnatifid, forming a handsome plant. It is the dried scraped stems of this plant that form the second ingredient in tonga.

Preservation of Flowers with their Natural Form and Color.

One of the processes consists, says *La Belgique Horticole*, in inclosing the flower or flowers in a glass jar provided with an air-tight, hollow ground-glass stopper, the cavity of which is filled with quicklime wrapped in leather. The object of the lime is to absorb the small quantity of humidity already existing in the jar or which might enter on a removal of the stopper. The dry air, deprived of its carbonic acid, occupying the jar, seems to brighten the color of the flowers and preserves them in their natural colors.

Mr. Corneil's other method consists in burying the flowers carefully in sand and then drying them. The most convenient receptacle that he finds for this purpose is a piece of paper wrapped in the form of a cone, the point being bent over so as to form a truncated cone. The desiccation may be effected at a temperature of 10° to 100°, but the method which gives the best results is desiccation in a vacuum in

the presence of commercial sulphuric acid or any other substance which absorbs water with avidity, such, for instance, as chloride of calcium or caustic potash. The flower once dried, which will be in eight or ten days, it must be removed from the sand with great care, for it is very fragile. The dust remaining on the petals is removed by allowing coarse sand to fall upon them from a small height. After this species of washing the specimen has received all the treatment necessary, and in this state may be preserved indefinitely if it be inclosed in a hermetically sealed jar along with a little quicklime.



SHELTERING HAY RICK.

and is rarely seen on the fish stands. Sothern, the actor, considered it a great luxury, and was known to pay very high prices to obtain it, being of the opinion that it contained more brain food than any other fish.

It is related of the Roman emperors that, so great was




MOUTH AND TEETH OF SEA LAMPREY.

their valuation of the lamprey, both as a luxury and stimulating food, artificial ponds were constructed in which to fatten the lampreys, the principal food used being well fattened living slaves, on whose bodies the eels would fasten and feed, affording an enjoyable pastime to the noble Roman.

The only place in New York city where the lamprey is served up is at the Grand Union Hotel.

At the next dinner of the Ichthyophagous Club, the sea



THE SEA LAMPREY.

The preservation of color in dried flowers, however, will not in all cases be attended with success, the action of light upon them being very variable. Certain kinds stand the light perfectly—even the direct light of the sun; others are even influenced by a diffused light, and there are some again that are discolored even in partial darkness. Three plants, *Abutilon schari*, *Prillaria imperialis*, and *Vanda suavis*, exhibit an unlooked-for phenomenon. When dried, these flowers become of a reddish-brown, but when they are exposed to the sun they assume a tint which is quite like their original one, except *Prillaria* (the crown-imperial), which becomes violet.

MECHANICAL INVENTIONS.

Mr. George W. Greene, corner 41st street and A. V. R. R., Pittsburg, Pa., has patented an improved machine for cutting tapered cork. This ingenious machine cannot be described without engravings.

A means by which the felly of a carriage, wagon, or other similar wheel may be enlarged for the purpose of tightening the tire of the wheel, has been patented by Mr. William Downham, of St. Johns, Mich.

A velocipede designed to be operated by two persons standing and applying their whole weight to the treadles, has been patented by Mr. Oliver U. Guinand, of Lawrenceburg, Ky. This vehicle is more easy to mount than the velocipedes in common use, and affords conveniences for carrying small parcels and packages.

An improved motive power has been patented by Mr. Obadiah W. Gibson, of Kellyville, Texas. This invention relates to improvements in motive powers by which the entire power of the horse is thrown on the shaft that operates the gear mechanism, which may be applied to the running of cotton gins, grist and flouring mills, and other purposes. The invention consists of an inclined wheel applied to a center shaft that turns in fixed bottom bearings and adjustable top bearings, and transmits the power by a crown wheel and gear wheels and shafts in one or both directions.

Messrs. Charles C. Henderson and Jacob R. Henderson, of Arkadelphia, Ark., have patented a machine adapted for measuring heavy cloths, bagging, and similar materials in lengths, as desired, in place of the usual method of measuring by hand. More particularly the object is to wind the material from the roll upon a suitable drum, measure the material as it is wound, and provide an indicator of the amount rolled off, so that the desired quantity can be wound and then cut off.

A simple machine for rapidly peeling vegetables or fruits, such as potatoes and apples, has been patented by Mr. Hervey Law, of Chatham, N. J. This machine is especially designed for peeling potatoes, which are usually of very irregular forms and sizes; and the invention consists in means whereby the latter may be quickly set to a longer or shorter travel to correspond to the length of the potato.

An improved cloth-measuring machine has been patented by Messrs. Charles C. Henderson and Jacob B. Henderson, of Arkadelphia, Ark. This improvement relates to machines for winding off and measuring bagging and heavy bolt goods, and is designed to save the time and labor required in doing such work by hand. It is especially calculated to relieve the counting shaft of weight from the passing web.

An improved device for removing fire damp from mines has been patented by Mr. Francis Wodiczka, of Graz, Austria. The invention consists in arranging a pipe or channel, provided with a series of suction funnels, along the ridge of all the galleries and adits of a mine, which channel is connected with a side channel, which, in turn, leads into the main or receiving channel, which is in communication with the gas flue or chimney.

Hot Water for the Heart.


In a letter to the *Lancet*, Dr. A. Pagli records the following observation: He states that in Paris he saw a case in which, under the inhalation of chloroform, the heart ceased to beat, and artificial respiration for ten minutes failed to restore circulation, when Dr. Labbé dipped a large cloth in boiling water and applied it to the region of the heart, with the result of immediately restoring the action of that organ.

THE London Iron Trade Exchange, of recent date, publishes a complete list of blast furnaces in and out of blast in the United Kingdom. From the returns it appears that out of the total 943 furnaces built, 593 are in blast and 350 are standing. There are probably 40 furnaces in various districts which are not included in the returns, but none of these have been in blast for many years, and they will never be relighted; others are dismantled, and some have never been completed. The returns from Derbyshire were imperfect, and the figures relating to that district may not be quite accurate, but as regards other districts, the figures, says the *Exchange*, may be relied on.

EXPLOSION OF A STEAM DRYING CYLINDER.

BY S. M. HARTWELL.

On the afternoon of July 10 a steam drying cylinder in the Staten Island dye house of Barrett & Nephews, about one mile south of the steamboat landing at Port Richmond, S. I., exploded, seriously injuring five persons. The sketch, Fig. 1, shows the cylinder at A, one of three driven by a small steam engine and used for drying piece goods. Fig. 2 is an enlarged detail of the head joint. The cylinder was made of copper, lined on its exterior surface, 80 inches diameter by 48 inches long. The copper shell was about one-tenth of an inch thick, brazed at its longitudinal seam and fixed upon a cast iron spool by means of wrought iron hoops shrunk upon the copper over the spoolhead shown in section, Fig. 2, in which B is the hoop, C the cast iron head, and A' a section of the copper. The copper was calked at the edge, between the hoop and head, to make it steam tight, and to support the head. The heads were flat, something less than three-quarters of an inch thick in the web, thickened at the periphery, as shown in Fig. 2. The barrel of the cast iron spool was hollow, having hollow wrought journals. The inlet and outlet pipes for the steam were half inch, and entered the journals through stuffing boxes. A small safety valve was fixed to the inlet pipe. This cylinder is said to have borne a test pressure of 100 pounds to the square inch, applied by the makers. This, however, may be an error. The cylinder was about three years old, but had lately been to the maker to be retinned, since when no one remembers to have seen steam escape from the safety



EXPLOSION OF A STEAM DRYING CYLINDER.

valve, although the weight was set for a light pressure. The cylinder was located with reference to its fellows at A, and about 150 feet from the steam boiler that supplied it with steam through a 1½ inch main and a half inch branch pipe.

The safety valves on the steam boilers, of which there were four horizontal tubular in this system, were weighted to blow at a limit of 50 pounds per square inch.

A small drip pipe was tapped into the barrel of the spool of the exploded cylinder at a right angle to its axis; that was for the purpose of carrying off the water of condensation, which was forced out intermittently as the end of the pipe dipped into the water in the bottom of the cylinder at each revolution, steam escaping in the interim. There was a valve opening inward to prevent collapse in case of an accidental vacuum in the cylinder.

On the day of the accident the cylinder, A, had been a short time in operation after standing for considerable time, when the right-hand head blew out as shown, knocking the cylinder, C, against the wall and breaking the frame. The exploded cylinder flew in a direct line of its axis to the left through an open archway, F, into an adjoining room, knocking down and breaking in pieces the squeezing machine, D, and its supporting posts; thence it struck and displaced the third drying cylinder, B, and landed in the corner, at A', a badly smashed concern, about 40 feet from its starting point. The concussion broke two windows, E and E', one in each room nearly in line, while a piece of the broken squeezer, D, was shot endwise through the window, E, into the dye house, breaking a man's arm.

During the experience of Captain C. W. Kennedy, the secretary and superintendent of the works, and that of the dyer, Mr. E. Parker, covering the thirty odd years of the existence of the Barrett dye house, drying cylinders have occasionally given out in a mild way, sometimes even leaving their places from the effect of the escaping steam. The absence of water, which no doubt was present in considerable quantity in this case, accounts for the difference.

THE HYPOTHESIS

In this case is that the safety valve had been damaged in the resetting or the removal of the cylinder for retinning, and that the outlet pipe for steam and water subsequently became choked with a wad of some kind that found its way into the cylinder while repairs were going on. Water accumulated from condensation of steam, which leaked into the cylinder while stopped, and on starting, the pressure in the generator being 40 to 50 pounds per square inch, gradually rose in the cylinder till its strength was exceeded, when it gave way as steam boilers sometimes do at the weakest point. The work of destruction is then accomplished by the explosion—sudden expansion—of the water which is suddenly relieved, the heat due to the difference of pressure escaping from every part of its mass with great violence.

PROTECTION FROM LIGHTNING.

During the present summer thus far no very remarkable damages from lightning in this part of the country have been reported. A few buildings have been struck and a few persons killed; but on the whole the losses of life and property have, we believe, been less than for some years past.

The oil regions of Pennsylvania have been remarkably exempt. Last season, as will be remembered, many oil tanks were struck and their contents burned. But this year, up to the present time, we hear of no oil burning from lightning. We believe that in quite a number of cases the owners of tanks have put up rods and earth connections, with the hope of saving their property. We should be glad if our correspondents in the oil country would send us notes of such improvements and take pains to observe and report the results if thunderstorms take place.

On the 12th of July a heavy thunderstorm passed over the cities of New York and Brooklyn with frequent and powerful discharges of lightning. The thousands of telegraph and telephone wires caused a general diffusion of the electric currents about town. In the SCIENTIFIC AMERICAN office there was a good deal of electrical snapping on the telephone conductors; while at the general Telephone Exchange and also at the Western Union Telegraph office there was an extensive display of this sort of fireworks. At all these offices the wire terminals are located in close proximity to conductors that are well grounded in the earth, and when lightning follows the wires into the buildings it simply leaps, with a spark and snap, to the ground conductor and

is dispersed. During the above storm the great seaside resort, near New York, known as the Manhattan Beach Hotel, situated at the edge of the ocean, Coney Island, was struck by lightning; fortunately no serious damage was done. Several thousand persons had sought shelter from the rain within the saloons and under the piazzas of the immense structure. A blinding flash and a deafening roar informed the multitude that the house had been struck. But none were injured. The building is 600 feet long, 100 feet broad, three stories high, and although well provided with almost every other convenience and apparatus for

safety, no precautions in respect to protection from lightning had been adopted. The several spires or steeples that rise from different parts of the building were surmounted by ornamental sprays or branches of iron, which would have formed excellent lightning rods had they been connected with the earth. After the storm we made a careful examination of the premises, and found that the lightning had struck the iron ornaments of the central tower, run down the iron staff thereof on to the wooden timbers within the spire, where the iron terminated; thence the electrical current continued down on the wooden rafters, splintering the same for a distance of about 30 feet to the ceiling of the topmost sleeping room, where it burst through the plastering and took to an adjacent gas pipe, on which the current went to the ground without further damage. It is obvious that all the iron work of the spires and roof trimmings should be connected by rods with the metal pipings in the ground, and doubtless this will now be done. The escape of the tower from fire, with the iron staff terminating in the middle of a mass of dry timbers, is quite fortunate.

We will here repeat the golden rule which must be observed if protection from lightning is expected, namely, the rod must have a large area of conducting material for its underground terminal. Everybody will understand the folly of embedding the extremity of the rod in the woodwork of a steeple, as in the foregoing example. But the majority of rods are not much better arranged, as the common practice is to stick the terminals of the rods two or three feet down into dry earth and call the job complete and safe. But the truth is, it is very unsafe; it is not a sufficient electrical earth connection. The extremity of the rod should be joined underground by soldered joints to the metallic water pipes, gas pipes, or drain pipes, in the absence of these metals then long trenches should be made, in which conducting material should be placed, such as a continuous layer, a few inches deep, of iron ore or coal dust—hard coal or charcoal—and the rod should be extended along the trench, in contact with the coal, which is a good conductor.

A Large Monolith.

At a granite quarry in Westerly, Rhode Island, there was recently detached a monolith 150 feet long, 10 feet wide, and 8 feet thick, weighing over 1,000 tons. These dimensions greatly exceed those of the Obelisk of Sennefer, the largest of the Egyptian monoliths. The Westerly stone, a proprietor, Mr. H. Q. French, says, was loosened by one oblong blast-hole in such a simple and perfect manner that the theories and conjectures advanced by many as to the methods of the Egyptians appear absurd. It contains over 12,000 cubic feet of granite, which, cut into smaller blocks, will fetch about \$50,000. Mr. French is quite positive that it could be brought to this city, finished as an obelisk, and erected for about \$150,000.

NEW BOOK ON MODERN MILLING JUST PUBLISHED.

Modern Milling. Being the substance of two addresses delivered by request of the Franklin Institute, Philadelphia, by Robert Armstrong, Ph.D., Illustrated by 25 engravings. 250 pages. \$2.00.

We also publish:
Coke. The Industrial American, Lignite and Milling by Robert Armstrong. Illustrated by wood engravings. 250 pages. \$2.00.
Hemp. The Industrial American, Lignite and Milling by Robert Armstrong. Illustrated by wood engravings. 250 pages. \$2.00.
Paper. The Industrial American, Lignite and Milling by Robert Armstrong. Illustrated by wood engravings. 250 pages. \$2.00.
The above are all of our Industrial and Technical Books, sent by mail free of postage at the publication price to any address in the world.

HENRY CAREY BAIRD & CO.,
Industrial Publishers, Booksellers, and Importers,
215 WALNUT STREET, PHILADELPHIA, PA.



SWEEPSTAKES WITH THE ELLIS
Patent Journal Box. The best Paper and Match ever made. Planning 30 in. wide, 24 in. thick, weight 2.25 lbs. 6500 planning 24 in. wide, 1 in. thick, weight 2.00 lbs. 6500. Binding, Arbor and Head, extra \$30. Each, 50c. and Ellis Machinery a specialty. Send for descriptive catalogue to Rowley & Hermann, Williamsport, Pa.

50 All Gold, Silver, and 100 Gold (No 2 at the same on 800). 1 Union Bros. Cantonville, Conn.

NEW YORK STAMP WORKS
Steel Letters, STAMPS, 87 NASSAU ST. N.Y.

Geo. W. Read & Co.,
Manufacturers and Dealers in
MAHOGANY,
And all Foreign and Domestic
Cabinet Woods.
SOLE MANUFACTURERS
CUT AND PRESS DRIED

THIN LUMBER,
FOR
CIGAR BOXES,
Panel Stock, Etc., Etc.

Mills and Warehouses:

186 to 200 Lewis St., New York.



THE NEW OTTO SILENT GAS ENGINE.

Useful for all work of small stationary steam engine. Runs on kerosene, gas, and 7 H.P. by SCHLEICHER, SCHLIMM & CO., 345 Chestnut Street, Phila., Pa. A. C. Manning, 38 Day St., New York, Agent.

WOOD-WORKING MACHINERY.

Our Universal Wood Workers, Planing, Matching, Moulding, Band and Hand Sawing Machines, Carriage, Wagon and Wheel Machinery, etc.
BENTEL, MARCANT & CO.,
HAMILTON, OHIO, U.S.A.

THE MEDART PATENT WROUGHT RIM PULLEY is the lightest, strongest, and most durable pulley ever made. **THE CHEAPEST PULLEY IN THE MARKET.** ANY SIZE IN STOCK. STRAIGHT OR CONCAVE. 100 LBS. TO 10 TONS. SINGLE OR DOUBLE. IN TRIPLE AND LARGE SIZES. SPECIALTY. THE HARTFORD ENGINEERING CO. HARTFORD CONN.

PATENTS.

MUNN, MUNN & CO., in connection with the publication of the SCIENTIFIC AMERICAN, continue to examine improvements, and to act as Solicitors of Patents for Inventions.

In this line of business they have had thirty-five years' experience, and now have expanded facilities for the preparation of Patent Drawings, specifications, and the presentation of Applications for Patents in the United States, Canada, and Foreign Countries. Messrs. Munn & Co. also attend to the preparation of Caveats, Copyrights for Books, Labels, Revisions, Assignments, and Reports on Infringements of Patents. All business entrusted to them is done with special care and promptness, on very reasonable terms.

A pamphlet sent free of charge, on application, containing full information about Patents and how to procure them; directions concerning Labels, Copyrights, Designs, Patents, Appeals, Revisions, Infringements, Assignments, Rejected Cases, Hints on the Sale of Patents, etc.

We also send, free of charge, a Synopsis of Foreign Patent Laws, showing the cost and method of securing patents in all the principal countries of the world.

MUNN & CO., Solicitors of Patents,
31 Park Row, New York.

BRANCH OFFICE—Corner of F and 7th Streets, Washington, D. C.

NEW YORK BELTING AND PACKING COMP'Y.

The Oldest and Largest Manufacturers of the Original
SOLID VULCANITE
EMERY WHEELS.
All other kinds of Belting and Packing. Our name is stamped in full upon all our standard BELTING, PACKING, and HOSE.
Address NEW YORK BELTING AND PACKING CO., NEW YORK.
Entire Wheel JOHN H. CHURCH, Treas.

Pond's Tools,

Knives, Lathes, Planers, Drills, &c.
DAVID W. POND, Worcester, Mass.



BIGB'S
Baltimore
FIRE-PLACE HEATERS
In warm and cool rooms.
The Standard, Best, and Most Economical
Tool for the world.
R. C. BIGB & SON
100 N. 1st St., Baltimore, Md.
Manufacturers of Fire-Place Heaters.
2nd Floor, 100 N. 1st St., Baltimore, Md.

CIVIL, MECHANICAL, AND MINING ENGINEERING at the Henshaw Polytechnic Institute, Troy, N. Y. The oldest engineering school in America. Next term begins September 15. The Register for 1881 contains a list of the graduates for the past 54 years, with their positions, also, course of study, requirements, expenses, etc. Address: **DAVID M. GREENE, Director.**

"BLAKE'S CHALLENGE" ROCK BREAKER.

Patented November 18, 1879.
For Macadam Road making, Ballasting of Railroads, Graveling Orns, and of Iron Furnaces, etc. Rapidly superseding our older style of Blake Crusher on account of its superior strength, efficiency, and simplicity. Adopted by important Railway and Mining Corporations, Cities, and Towns. First Class Medal of Superiority awarded by American Institute, 1879 and 1880.
BLAKE CRUSHER CO., Sole Makers, New Haven, Conn.

MACHINERY

of every description. 121 Chambers and 123 Rensselaer Sts., New York. THE UNION PLACE MACHINERY AGENCY.

BEATTY'S OILS. 18 useful oils, 5 sets roads, only \$45. Planes, \$125 up. 127 Duane. Catalogue FREE. Address **BEATTY, Washington, N. J.**

DEAN BROTHERS,
Steam Pump Works,
INDIANAPOLIS, IND.,
Manufacturers of
BOILER FEEDERS AND PUMPING MACHINERY.
FOR ALL PURPOSES.
Send for new Illustrated Catalogue.

NOW READY. The New Edition of Trautwine's Civil Engineer's Pocket Book. 12mo, 600 pages, illustrated with 600 engravings from original designs. Fifteenth thousand. Revised, corrected, and enlarged. **E. CLAXTON & CO., 100 Market St., Philadelphia, Pa.**

SUPERIOR SUBSTITUTE FOR WOOD ENGRAVING.
MOSS ENGRAVING CO.
333 PEARL STREET, COR. RLM, NEW YORK.
Engravings of Portraits, Buildings, Landscapes, Machinery, Maps, Etc., for Newspapers, Books, Catalogues, Etc. Much cheaper than Wood Cut.
THE LARGEST ESTABLISHMENT OF THE KIND IN THE WORLD.

WHEELER'S PATENT WOOD FILLER
Fills the pores of wood perfectly, so that smooth finish is obtained with one coat of varnish. Send for circular. Mention this paper.
BRIDGEPORT WOOD FINISHING CO.,
30 Blocker Street, New York.

PATENT QUICK
Adjustable Stroke
SHAPERS
Can be changed while in Motion.
B. GOULD & EBERHARDT,
NEWARK, N. J.

\$50 Per week. INTELLIGENT AGENTS can earn with the **Walke Flexible Fountain Gold Pen.** No expense for ink. Write four days without stopping. Only first-class work need apply. Address **WALKE PEN MFG CO.,** Hamilton, Ohio, or 31 Broadway, New York.

\$5 to \$20 per day at home. Samples worth \$5 free. Address **STROSS & Co., Portland, Me.**

DUC'S ELEVATOR BUCKET,
For use in Grains Elevators, Flour Mills, Sugar Refineries, and Mills of every kind. They are made of Charcoal Impregnated Iron, extra strong and durable. Have no rivets to catch. 300,000 in use.
THOS. F. ROWLAND, Sole Manufacturer, Brooklyn, N. Y.

PATENTS SOLD
Just Stock Companies formed. Stock placed for immediate sale. Good investments always on hand. Highest references given. Circulars free. **J. L. BICK-ALLEN & CO., BROKERS, 733 BROADWAY, New York.**

OLD RELIABLE
NO FAILURE IN SIXTEEN YEARS
HEALD & MORRIS CENTRIFUGAL PUMPS
100 TO 35,000 GALLONS PER MINUTE CAPACITY
HEALD & MORRIS, Baldwinsville, N.Y.

FOR SECOND-HAND ENGINES,
Address **MARRIS IRON WORKS, Titusville, Pa.**

\$66 a week in your own town. Terms and \$5 outfit free. Address **H. HALLITT & Co., Portland, Me.**

FORSTER'S CRUSHER AND CRUSHER AND PULVERIZER,
The simplest machine ever devised for the purpose. We warrant 50 per cent. advantage in crushing with one-third power, and in combined crushing and pulverizing the work of stamp and mills at one-third first cost. Can be operated with any kind of power.
Address **TOTTEN & CO., Pittsburg, Pa.**

PROSPECTING MINERAL LANDS A SPECIALTY.
CYLINDRICAL SECTIONS OR CORES OBTAINED THE WHOLE DISTANCE WORKED. ARTESIAN WELLS. BORED ROUNDS AND STRAIGHT ADMITTING A LARGER PUMP AND CASING.
IN PROPORTION TO SIZE OF WELL TAKEN BY ANY OTHER PROCESS. ESTIMATES GIVEN AND CONTRACTS MADE BY
TENNESSEE & VIRGINIA DIAMOND DRILL CO.
DIAMOND DRILLING AND MINING. ALL KINDS OF DRILLING. SINKING. &c.

MACHINISTS' TOOLS.
NEW AND IMPROVED PATTERNS.
Send for new Illustrated Catalogue.
Lathes, Planers, Drills, &c.
NEW HAVEN MANUFACTURING CO.,
New Haven, Conn.

JAS. MURDOCK JR., CINCINNATI
BRASS, COPPER, SILVER.
WARRANTED SWEET & PURE IN THE THREE METALS. 100%.

HOW TO SOFTEN HARD WATER.
Description of Dr. Clarke's simple process for softening hard waters, and at the same time purifying the water. This paper is of much value and interest. Contributed to SCIENTIFIC AMERICAN SUPPLEMENT, No. 279. Price 10 cents. To be had at this office and from all news-dealers.

DO YOUR OWN PRINTING
Presses and outfits from \$3 to \$200.
Over 2,000 styles of type. Catalogue and reduced price list free.
H. HOOVER, Phila., Pa.

RUPTURE
cured without an operation or the injury to the system inflicted by Dr. J. A. SHERMAN'S method. Office, 254 Broadway, New York. His book with photographic illustrations of bad cases, before and after cure, mailed for 10c.

DEAF
PECK'S PATENT INVISIBLE EAR DRUMS.
A Grand Success. Send for treatise.
123 N. 3d St.,
533 Broadway, New York.
Also 100 N. 3d St., between 1st and 2nd Sts.

\$72 A WEEK. \$10 a day at home easily made. Costly outfit free. Address **TUTE & Co., Augusta, Me.**

PAYNE'S AUTOMATIC ENGINES.
Established 1840.
Spark Attacher.
Reliable, durable, and economical. Will furnish a horse power with one-third less fuel and water than any other engine built and fitted with an automatic cut-off. Send for Illustrated Catalogue. A. J. Payne, for information and prices.
B. W. PAYNE & SONS,
Box 1407,
Corning, N. Y.

THE SCOVILL
"Pop" Safety Valve,
SIMPLE, RELIABLE, DURABLE.
For Locomotive, Stationary, Marine, and Portable Boilers.
Send for descriptive circulars and price lists to
THE HANCOCK INSPIRATOR CO.,
BOSTON, MASS.

BOOKWATER ENGINE.
Compact, substantial, economical, and easily managed; guaranteed to work well and give full power claimed. Engine and boiler complete including driver, pump, etc., at the low price of
1 HORSE POWER \$70 00
2 " " 120 00
3 " " 150 00
4 " " 180 00
5 " " 210 00
6 " " 240 00
7 " " 270 00
8 " " 300 00
9 " " 330 00
10 " " 360 00
12 " " 420 00
15 " " 510 00
18 " " 600 00
20 " " 660 00
25 " " 825 00
30 " " 990 00
35 " " 1155 00
40 " " 1320 00
45 " " 1485 00
50 " " 1650 00
55 " " 1815 00
60 " " 1980 00
65 " " 2145 00
70 " " 2310 00
75 " " 2475 00
80 " " 2640 00
85 " " 2805 00
90 " " 2970 00
95 " " 3135 00
100 " " 3300 00
110 " " 3630 00
120 " " 3960 00
130 " " 4290 00
140 " " 4620 00
150 " " 4950 00
160 " " 5280 00
170 " " 5610 00
180 " " 5940 00
190 " " 6270 00
200 " " 6600 00
220 " " 7260 00
240 " " 7920 00
260 " " 8580 00
280 " " 9240 00
300 " " 9900 00
320 " " 10560 00
340 " " 11220 00
360 " " 11880 00
380 " " 12540 00
400 " " 13200 00
420 " " 13860 00
440 " " 14520 00
460 " " 15180 00
480 " " 15840 00
500 " " 16500 00
520 " " 17160 00
540 " " 17820 00
560 " " 18480 00
580 " " 19140 00
600 " " 19800 00
620 " " 20460 00
640 " " 21120 00
660 " " 21780 00
680 " " 22440 00
700 " " 23100 00
720 " " 23760 00
740 " " 24420 00
760 " " 25080 00
780 " " 25740 00
800 " " 26400 00
820 " " 27060 00
840 " " 27720 00
860 " " 28380 00
880 " " 29040 00
900 " " 29700 00
920 " " 30360 00
940 " " 31020 00
960 " " 31680 00
980 " " 32340 00
1000 " " 33000 00
1100 " " 36300 00
1200 " " 39600 00
1300 " " 42900 00
1400 " " 46200 00
1500 " " 49500 00
1600 " " 52800 00
1700 " " 56100 00
1800 " " 59400 00
1900 " " 62700 00
2000 " " 66000 00
2200 " " 72600 00
2400 " " 79200 00
2600 " " 85800 00
2800 " " 92400 00
3000 " " 99000 00
3200 " " 105600 00
3400 " " 112200 00
3600 " " 118800 00
3800 " " 125400 00
4000 " " 132000 00
4200 " " 138600 00
4400 " " 145200 00
4600 " " 151800 00
4800 " " 158400 00
5000 " " 165000 00
5200 " " 171600 00
5400 " " 178200 00
5600 " " 184800 00
5800 " " 191400 00
6000 " " 198000 00
6200 " " 204600 00
6400 " " 211200 00
6600 " " 217800 00
6800 " " 224400 00
7000 " " 231000 00
7200 " " 237600 00
7400 " " 244200 00
7600 " " 250800 00
7800 " " 257400 00
8000 " " 264000 00
8200 " " 270600 00
8400 " " 277200 00
8600 " " 283800 00
8800 " " 290400 00
9000 " " 297000 00
9200 " " 303600 00
9400 " " 310200 00
9600 " " 316800 00
9800 " " 323400 00
10000 " " 330000 00
11000 " " 363000 00
12000 " " 396000 00
13000 " " 429000 00
14000 " " 462000 00
15000 " " 495000 00
16000 " " 528000 00
17000 " " 561000 00
18000 " " 594000 00
19000 " " 627000 00
20000 " " 660000 00
22000 " " 726000 00
24000 " " 792000 00
26000 " " 858000 00
28000 " " 924000 00
30000 " " 990000 00
32000 " " 1056000 00
34000 " " 1122000 00
36000 " " 1188000 00
38000 " " 1254000 00
40000 " " 1320000 00
42000 " " 1386000 00
44000 " " 1452000 00
46000 " " 1518000 00
48000 " " 1584000 00
50000 " " 1650000 00
52000 " " 1716000 00
54000 " " 1782000 00
56000 " " 1848000 00
58000 " " 1914000 00
60000 " " 1980000 00
62000 " " 2046000 00
64000 " " 2112000 00
66000 " " 2178000 00
68000 " " 2244000 00
70000 " " 2310000 00
72000 " " 2376000 00
74000 " " 2442000 00
76000 " " 2508000 00
78000 " " 2574000 00
80000 " " 2640000 00
82000 " " 2706000 00
84000 " " 2772000 00
86000 " " 2838000 00
88000 " " 2904000 00
90000 " " 2970000 00
92000 " " 3036000 00
94000 " " 3102000 00
96000 " " 3168000 00
98000 " " 3234000 00
100000 " " 3300000 00
110000 " " 3630000 00
120000 " " 3960000 00
130000 " " 4290000 00
140000 " " 4620000 00
150000 " " 4950000 00
160000 " " 5280000 00
170000 " " 5610000 00
180000 " " 5940000 00
190000 " " 6270000 00
200000 " " 6600000 00
220000 " " 7260000 00
240000 " " 7920000 00
260000 " " 8580000 00
280000 " " 9240000 00
300000 " " 9900000 00
320000 " " 10560000 00
340000 " " 11220000 00
360000 " " 11880000 00
380000 " " 12540000 00
400000 " " 13200000 00
420000 " " 13860000 00
440000 " " 14520000 00
460000 " " 15180000 00
480000 " " 15840000 00
500000 " " 16500000 00
520000 " " 17160000 00
540000 " " 17820000 00
560000 " " 18480000 00
580000 " " 19140000 00
600000 " " 19800000 00
620000 " " 20460000 00
640000 " " 21120000 00
660000 " " 21780000 00
680000 " " 22440000 00
700000 " " 23100000 00
720000 " " 23760000 00
740000 " " 24420000 00
760000 " " 25080000 00
780000 " " 25740000 00
800000 " " 26400000 00
820000 " " 27060000 00
840000 " " 27720000 00
860000 " " 28380000 00
880000 " " 29040000 00
900000 " " 29700000 00
920000 " " 30360000 00
940000 " " 31020000 00
960000 " " 31680000 00
980000 " " 32340000 00
1000000 " " 33000000 00
1100000 " " 36300000 00
1200000 " " 39600000 00
1300000 " " 42900000 00
1400000 " " 46200000 00
1500000 " " 49500000 00
1600000 " " 52800000 00
1700000 " " 56100000 00
1800000 " " 59400000 00
1900000 " " 62700000 00
2000000 " " 66000000 00
2200000 " " 72600000 00
2400000 " " 79200000 00
2600000 " " 85800000 00
2800000 " " 92400000 00
3000000 " " 99000000 00
3200000 " " 105600000 00
3400000 " " 112200000 00
3600000 " " 118800000 00
3800000 " " 125400000 00
4000000 " " 132000000 00
4200000 " " 138600000 00
4400000 " " 145200000 00
4600000 " " 151800000 00
4800000 " " 158400000 00
5000000 " " 165000000 00
5200000 " " 171600000 00
5400000 " " 178200000 00
5600000 " " 184800000 00
5800000 " " 191400000 00
6000000 " " 198000000 00
6200000 " " 204600000 00
6400000 " " 211200000 00
6600000 " " 217800000 00
6800000 " " 224400000 00
7000000 " " 231000000 00
7200000 " " 237600000 00
7400000 " " 244200000 00
7600000 " " 250800000 00
7800000 " " 257400000 00
8000000 " " 264000000 00
8200000 " " 270600000 00
8400000 " " 277200000 00
8600000 " " 283800000 00
8800000 " " 290400000 00
9000000 " " 297000000 00
9200000 " " 303600000 00
9400000 " " 310200000 00
9600000 " " 316800000 00
9800000 " " 323400000 00
10000000 " " 330000000 00
11000000 " " 363000000 00
12000000 " " 396000000 00
13000000 " " 429000000 00
14000000 " " 462000000 00
15000000 " " 495000000 00
16000000 " " 528000000 00
17000000 " " 561000000 00
18000000 " " 594000000 00
19000000 " " 627000000 00
20000000 " " 660000000 00
22000000 " " 726000000 00
24000000 " " 792000000 00
26000000 " " 858000000 00
28000000 " " 924000000 00
30000000 " " 990000000 00
32000000 " " 1056000000 00
34000000 " " 1122000000 00
36000000 " " 1188000000 00
38000000 " " 1254000000 00
40000000 " " 1320000000 00
42000000 " " 1386000000 00
44000000 " " 1452000000 00
46000000 " " 1518000000 00
48000000 " " 1584000000 00
50000000 " " 1650000000 00
52000000 " " 1716000000 00
54000000 " " 1782000000 00
56000000 " " 1848000000 00
58000000 " " 1914000000 00
60000000 " " 1980000000 00
62000000 " " 2046000000 00
64000000 " " 2112000000 00
66000000 " " 2178000000 00
68000000 " " 2244000000 00
70000000 " " 2310000000 00
72000000 " " 2376000000 00
74000000 " " 2442000000 00
76000000 " " 2508000000 00
78000000 " " 2574000000 00
80000000 " " 2640000000 00
82000000 " " 2706000000 00
84000000 " " 2772000000 00
86000000 " " 2838000000 00
88000000 " " 2904000000 00
90000000 " " 2970000000 00
92000000 " " 3036000000 00
94000000 " " 3102000000 00

Advertisements.

Inside Page, each insertion - - - 75 cents a line.
Back Page, each insertion - - - \$1.00 a line.
(About eight words to a line.)

Drawings may lead advertisements at the same rate per line, by arrangement, at the latter price. Advertisements must be received at publication office as early as Tuesday morning to appear in next issue.

Established **EAGLE ANVILS, 1843.**

Solid CAST STEEL, Face and Horn. Are Fully Warranted. Retail Price, 10 cts. per lb.

Double Screw, Parallel, Leg Vises.

Made and WARRANTED stronger than any other Vise by FISHER & NORRIS only, Trenton, N. J.

"1880" Lane Cutter, by mail, 50c. Discount to the trade, Sterling, Elliot, 32 Dover St., Boston, Mass.

ENSILAGE POWER! Our 2-Horse Eureka

Feed and Boiler is just the thing—SAFE, CONVENIENT, DURABLE.
R. W. PAYNE & SONS, COVING, N. Y.

BOILER COVERINGS,

ASBESTOS-LINED, REMOVABLE.
THE PATENT AIR SPACE COVERINGS.
THE CHALMERS-SPENCER CO., Sole Proprietors,
10 Cortlandt St., Foot of East 9th St., New York.

FOR SALE—Steam Mill in North part of State. New first-class engine and machinery. Beside railroad. Good location for chair, broom, and fork handle, or other wood manufacture. A bargain for cash.
W. M. BROWN, 12 Broadway, New York.

H.W. JOHNS' ASBESTOS LIQUID PAINTS,

ASBESTOS ROOFING.
ASBESTOS BOILER COVERINGS.
ASBESTOS LINING FELT.
ASBESTOS STEAM PACKING.
ASBESTOS WICK PACKING.
ASBESTOS FLAT PACKING.
ASBESTOS MILLBOARD.
ASBESTOS GASKETS.
ASBESTOS SHEATHINGS.
COATINGS, CEMENTS, Etc.

Descriptive price lists and samples sent free.

H. W. JOHNS M'F'G CO.,
87 Maiden Lane, New York.

BARREL, KEG, HOSSHEAD, AND STAVE MACHINERY.
Over 50 varieties manufactured by
E. & B. HOLMES,
Buffalo, N. Y.
Best Running.
True Hoop Drilling.

FOR SALE—U. S. PATENT OF VALUABLE FLOURING MILL MACHINE. Very popular and profitable. E. C. Box 714, New York.

NEW YORK BELTING AND PACKING
Wellington Mills Emery
Used in ONLY our Wheels.
37 & 38 PARK ROW, NEW YORK.

WIRE ROPE
Address JOHN A. ROEBLING'S SONS, Manufacturers, Trenton, N. J., or 111 Liberty Street, New York.
Wheels and Rope for conveying power long distances. Send for circular.

FRIEDMANN'S PATENT INJECTOR.
THE BEST

Boiler Feeder
Simple, Reliable, and Effective.
40,000 IN ACTUAL USE.
NATHAN & DREYFUS,
Sole Manufacturers, NEW YORK.
Send for Descriptive Catalogue

SHEET METAL DROP PRESSES.
STILES & PARKER PRESS CO., Middletown, Conn.

HOLCOMB'S NEW Amplifying Telephones,
FOR PRIVATE LINES.
The latest and best. Patented April 26, 1881. These new instruments embody recent and important improvements. They transmit conversation, music, orders, etc., with almost electric speed and surprising clarity. The only durable and reliable substitute for the Electric Telephone. Work 100 miles. Price \$10 per set. Illustrated Circulars FREE.

HOLCOMB & CO.,
Maitland Creek, O.

Mill Stones and Corn Mills.
We make heavy Millstones, Portable Mills, Stone Machines, Packers, Mill Poles, Water Wheels, Pulleys, and Gearing specially adapted to Flour Mills. Send for catalogue.
J. T. NOYE & SONS, Buffalo, N. Y.

HOLDERS USE FOR A WEEK'S USE ANY GOOD INK MAY BE USED.
The Mackinnon Iridium Pen or Fluid Pencil.

THE ONLY RESERVOIR PEN IN THE WORLD WITH A CIRCLE OF IRIIDIUM AROUND THE POINT. Always ready. Always with you. Cannot blot. Cannot be worn out in a lifetime. MACKINNON PEN CO., 192 BROADWAY, CORNER JOHN STREET, NEW YORK. General Supply Depots in all principal cities in America and Europe.

Applied to all machinery driven by flywheels and liable to be broken by power stored in wheels, such as roller mills, spinning machines, presses, and wire drawing machines. We warrant to save gear and all machinery from breaking by using our rollers. Starts gradual stops quick. Any amount of power controlled. Friction Hoisting Engines and Brakes also, safety elevators. Can be run faster and stop quicker than any other friction. D. Frisbie & Co., New Haven, Ct.

ICE AT \$1.00 PER TON.
PICTET ARTIFICIAL ICE CO., Limited,
P. O. Box 300, 142 Greenwich St., New York.
Guaranteed to be the most efficient and economical of all existing ice and Cold Air Machines.

Jenkins' Patent Packing and Valves.
THE STANDARD.
Jenkins' Packing has never failed to make a perfect joint where directions were followed. Jenkins' Valves are warranted steam tight and are made of the best steam metal. JENKINS BROS., 71 John St., New York.

SHAFTS PULLEYS HANGERS
At Low Prices. Large Assorted Stock.
A. & F. BROWN, 37-41 Lewis St., New York.

ROOFING.
For steep or flat roofs. Applied by ordinary workmen at one-third the cost of tin. Circulars and samples free. Agents Wanted. T. NEW, 21 John Street, New York.

Jarvis Furnace Co.
Patent setting for Steam Boilers Burns Screenings and Street Coal without Blast. No. 1 Oliver St., Boston; No. 32 Liberty St., New York; No. 20 Market St., St. Louis; No. 1 Second St., Baltimore.

THE BACKUS WATER MOTOR
SUPPLIES FROM HYDRANT PRESSURE the cheapest power known. Invaluable for blowing Church Organs, running Presses, Trusses, Sewing Machines, in Household Turning Lathes, Scroll Saws, Grindstones, Coffee Mills, Sausage Machines, Food Cutters, Electric Lights, Dryers, etc. It needs little room, no blast, no hot water, no steam, no smoke, no noise, no coal, no oil, no expense, most compact, steady, will work at any pressure of water above 15 lbs. at 40 lbs. pressure has 4-horse power, and capacity up to 10 horse power. Prices from \$15 to \$300. Send for circular to THE BACKUS WATER MOTOR CO., Newark, N. J., or 325 Broadway, New York.

THE J. L. MOTT IRON WORKS,
88 and 90 Beckman St., New York.
Demarest's Patent Water Closers used almost exclusively in all fine work. Demarest's Water Closets, Latrines and Toilets for public buildings and factories. Mott's Celebrated Porcelain Lined Baths unequalled for beauty and cleanliness. Sanitary Goods of all kinds.

FOR BEST COLD PENS.
Send for Price List to JOHN HOLLAND, Mfr., 12 West 4th St., Cincinnati.

ROCK DRILLS, COMPRESSORS, FUSE, BATTERIES, POWDER.
ROLLESTONE LATHE.
Improvement over the Weymouth Lathe.
Latest Improved. Rotary and Stationary Bed Planers and Saw Planers. Band saws, Woodcutting Machines, Steam, Hand, and Horse Power. Boring Machines, etc. Also large stock of Second-hand Machinery consisting of Machinists' Tools, Wood Working Machinery, Engines, Boilers, on hand. Send stamp for catalogue, and state just what you want to ROLLESTONE MACHINE CO., 45 Water St., Fitchburg, Mass.

MACHINISTS' TOOLS.
Iron Planing Machines
A SPECIALTY.
WHITCOMB MFG. CO., Worcester, Mass.

W. A. HARRIS, PROVIDENCE, R. I. (PARK STREET).
Six minutes' work. West from station.
Original and Only builder of the
HARRIS-CORLISS ENGINE
With Harris' Patented Improvements, from 10 to 1,000 H. P.

STUTTERING cured by Hare's appliances. Send for description to SIMPSON & CO., Box 226, New York.

KORTING UNIVERSAL INJECTOR
FOR BOILER FEEDING
Send for CIRCULAR
PHILADELPHIA, WASHINGTON, ST. LOUIS, NEW YORK, CHICAGO, PITTSBURGH, CLEVELAND, ALBANY, N. Y.

HARTFORD STEAM BOILER
Inspection & Insurance
COMPANY.
W. B. FRANKLIN, Pres't. J. M. ALLEN, Pres't.
J. B. PIERCE, Sec'y.

SAWS 40,000
EMERSON'S PATENT SAWYERS' HAND BOOKS
(FREE) "ANY PART OF THE WORLD."
EMERSON, SMITH & CO., BEAVER FALLS, PA.

ESTABLISHED 1841.
JOSEPH C. TODD,
Successor to
TODD & RAFFERTY, PATERSON, N. J.,
Engineer and Machinist,

Boiler, Pump, Jute, Rope, Oakum, and Flagging Machinery, Steam Engines, Boilers, etc. Sole agent for Mayhew's New Patent Acme Steam Engine and Force Pump combined. Also owner and exclusive manufacturer of
The New Baxter Patent Portable Steam Engine.

These engines are admirably adapted to all kinds of light power for driving
PRINTING PRESSES,

pumping water, sawing wood, grinding coffee, ginning cotton, and all kinds of agricultural and mechanical purposes, and are furnished at the following low prices:

1 Horse Power, \$150 1 1/2 Horse Power, \$190
2 Horse Power, 245 2 1/2 Horse Power, 275
3 Horse Power, 290 4 Horse Power, 350

Send for descriptive circular. Address
J. C. TODD, Paterson, N. J.,
Or No. 10 Barclay St., New York.

THE NEW BAXTER PATENT PORTABLE STEAM ENGINE.
These engines are admirably adapted to all kinds of light power for driving
PRINTING PRESSES,

pumping water, sawing wood, grinding coffee, ginning cotton, and all kinds of agricultural and mechanical purposes, and are furnished at the following low prices:

1 Horse Power, \$150 1 1/2 Horse Power, \$190
2 Horse Power, 245 2 1/2 Horse Power, 275
3 Horse Power, 290 4 Horse Power, 350

Send for descriptive circular. Address
J. C. TODD, Paterson, N. J.,
Or No. 10 Barclay St., New York.

THE NEW BAXTER PATENT PORTABLE STEAM ENGINE.
These engines are admirably adapted to all kinds of light power for driving
PRINTING PRESSES,

pumping water, sawing wood, grinding coffee, ginning cotton, and all kinds of agricultural and mechanical purposes, and are furnished at the following low prices:

1 Horse Power, \$150 1 1/2 Horse Power, \$190
2 Horse Power, 245 2 1/2 Horse Power, 275
3 Horse Power, 290 4 Horse Power, 350

Send for descriptive circular. Address
J. C. TODD, Paterson, N. J.,
Or No. 10 Barclay St., New York.

THE NEW BAXTER PATENT PORTABLE STEAM ENGINE.
These engines are admirably adapted to all kinds of light power for driving
PRINTING PRESSES,

pumping water, sawing wood, grinding coffee, ginning cotton, and all kinds of agricultural and mechanical purposes, and are furnished at the following low prices:

1 Horse Power, \$150 1 1/2 Horse Power, \$190
2 Horse Power, 245 2 1/2 Horse Power, 275
3 Horse Power, 290 4 Horse Power, 350

Send for descriptive circular. Address
J. C. TODD, Paterson, N. J.,
Or No. 10 Barclay St., New York.

THE NEW BAXTER PATENT PORTABLE STEAM ENGINE.
These engines are admirably adapted to all kinds of light power for driving
PRINTING PRESSES,

pumping water, sawing wood, grinding coffee, ginning cotton, and all kinds of agricultural and mechanical purposes, and are furnished at the following low prices:

THE New York Ice Machine Company,
115 Broadway, New York, Room 74.

LOW PRESSURE BINARY ABSORPTION SYSTEM.
Machines Making

ICE AND COLD AIR.
Low Pressure when running. No pressure at rest. Machines guaranteed by C. H. Delamater & Co.

TO INVENTORS
THE
Howard Manufacturing Co.
(INCORPORATED.)
364 & 366 Broadway, New York.

Organized for the manufacture and introduction of
PATENTED NOVELTIES
AND
YANKEE NOTIONS,
OF EVERY DESCRIPTION.
AMPLE CAPITAL.
Latest Improved Machinery.
CONNECTIONS WITH ALL WHOLESALE MERCHANTS
IN THE UNITED STATES AND CANADA.
Agents in Foreign Countries.
Correspondence without charge, with all who desire their inventions in our line developed.

PROSPECTUS
OF THE
Scientific American
FOR 1881.

The Most Popular Scientific Paper in the World.
VOLUME XLV. NEW SERIES.
COMMENCES JULY 1.

Only \$3.20 a Year, including postage. Weekly.
32 Numbers a Year.

This widely circulated and splendidly illustrated paper is published weekly. Every number contains sixteen pages of useful information, and a large number of original engravings of new inventions and discoveries, representing Engineering Works, Steam Machinery, New Inventions, Novelties in Mechanics, Manufactures, Chemistry, Electricity, Telegraphy, Photography, Architecture, Agriculture, Horticulture, Natural History, etc.

All Classes of Readers find in THE SCIENTIFIC AMERICAN a popular means of the best scientific information of the day; and it is the aim of the publishers to present it in an attractive form, avoiding as much as possible abstruse terms. To every intelligent mind, this journal affords a constant supply of instructive reading. It is promulgator of knowledge and progress in every community where it circulates.

Terms of Subscription.—One copy of THE SCIENTIFIC AMERICAN will be sent for one year—22 numbers—postage prepaid, to any subscriber in the United States or Canada, on receipt of three dollars and twenty cents by the publishers; six months, \$1.50; three months, \$1.00.

Clubs.—One extra copy of THE SCIENTIFIC AMERICAN will be supplied gratis for every club of five subscribers at \$3.20 each; additional copies at same proportionate rate.

One copy of THE SCIENTIFIC AMERICAN and one copy of THE SCIENTIFIC AMERICAN SUPPLEMENT will be sent for one year, postage prepaid, to any subscriber in the United States or Canada, on receipt of seven dollars by the publishers.

The safest way to remit is by Postal Order, Draft, or Express. Money carefully placed inside of envelope, securely sealed, and correctly addressed, seldom goes astray, but is at the sender's risk. Address all letters and make all orders, drafts, etc., payable to

MUNN & CO.,
37 Park Row, New York.

To Foreign Subscribers.—Under the facilities of the Postal Union, THE SCIENTIFIC AMERICAN is now sent by post direct from New York, with regularity, to subscribers in Great Britain, India, Australia, and all other British colonies; to France, Austria, Belgium, Germany, Russia, and all other European States; Japan, Brazil, Mexico, and all States of Central and South America. Terms, when sent to foreign countries, Canada excepted, \$4.50, for SCIENTIFIC AMERICAN, 1 year; \$3.00, for both SCIENTIFIC AMERICAN and SUPPLEMENT for 1 year. This includes postage, which we pay. Remit by postal order or draft to order of Munn & Co., 37 Park Row, New York.

PRINTING INKS.
THE "Scientific American" is printed with CHAS. T. ENST JOHNSON & CO.'S INK. Tenth and Lombard Sts., Philadelphia, and 20 Gold St., New York.